### Prop K Grouped Allocation Requests March 20, 2018 Board Action

### **Table of Contents**

No.	Fund Source	Project Sponsor <sup>1</sup>	Expenditure Plan Line Item/ Category Description	Project Name	Fund Reques		Page No.	
1	Prop K	SFMTA	Guideways - Muni	Cable Car Pulley Rebuild	Construction	\$ 2	280,999	1
2	Prop K	SFMTA	Upgrades to Major Arterials	19th Avenue Complete Streets	Construction	\$ 4	125,000	13
3	Prop K	SFMTA	New Signals & Signs	New Traffic Signals (Contract 64)	Construction	\$ 5,2	289,722	25
4	Prop K	SFMTA	Advanced Technology and Information Systems (SFgo)	Intelligent Transportation Systems - Variable Message Signs	Construction	\$ 1,0	000,000	53
5	Prop K	SFMTA	Advanced Technology and Information Systems (SFgo)	Intelligent Transportation Systems - Traffic Camera Deployment	Construction	\$ 1,2	200,000	67
6	Prop K	SFMTA	Traffic Calming, Pedestrian Circulation/ Safety	District 11 Near-Term Traffic Calming [NTIP Capital]	Design, Construction	\$ (	500,000	83
				Total Requested		\$ 8,7	795,721	

<sup>&</sup>lt;sup>1</sup> Acronyms: SFMTA (San Francisco Municipal Transportation Agency).



280,999

### San Francisco County Transportation Authority Prop K/Prop AA Allocation Request Form

FY of Allocation Action: 2017/18

Project Name: Cable Car Pulley Rebuild

**Grant Recipient:** San Francisco Municipal Transportation Agency - MUNI

### EXPENDITURE PLAN INFORMATION

Prop K EP category: Guideways: (EP-22)

Prop K EP Line Number (Primary): 22

Prop K Other EP Line Numbers:

\_\_\_\_

Current Prop AA Request: \$

Current Prop K Request: \$

Supervisorial District(s): District 02, District 03

Prop AA Category:

**REQUEST** 

### **Brief Project Description (type below)**

The SFMTA requests funding to rebuild the 25 sheaves (i.e. large pulleys) that allow the traction cable to move throughout the cable car system. The sheaves have reached the end of their useful lives.

### Detailed Scope, Project Benefits and Community Outreach (type below)

The City of San Francisco has 3 cable car lines: California Street, Powell-Hyde, and Powell-Mason. A cable car is pulled along rails by latching onto a moving cable inside a channel beneath the street. Each cable runs at a constant speed of 9.5 miles per hour and is driven by a 510 horsepower electric motor via an intricate system of pulleys and sheaves.

The SFMTA is planning to rebuild the rotating portions of the large sheaves with new shafts, bearings, and seals, and to replace the lubrication system. These vital components are at the end of their useful lives and need to be overhauled. See attached for the eleven locations of the 25 cable car system sheaves. The sheave rebuild effort will parallel the cable car gearbox overhaul project that began in September 2017; most of the work will be performed concurrently to minimize down time. It is critical to overhaul these components to ensure that the cable cars are running safely and to prevent a catastrophic failure that could result in an out-of-service condition lasting weeks as the SFMTA procures and manufactures replacement parts.

The work will be done by SFMTA personnel, and will be coordinated with a concurrent project rebuilding the main cable system gearboxes in the Cable Car Barn. SFMTA will rebuild the sheaves according to the original design, so no design work is required prior to construction. The majority of work will occur during service shutdowns planned for the Cable Car Propulsion Gearboxes project. Any remaining work will be scheduled to coincide with normal scheduled maintenance; there may be minor shutdowns of a few hours, but not for an entire day.

### **Project Location (type below)**

The 11 specific locations of the sheaves are as follows: Cable Car Barn at 1201 Mason Street; intersections at Washington and Mason Streets, Powell and Washington Streets, Beach & Hyde Streets, California & Mason Streets, Bay & Taylor Streets, Powell & Market Streets, California & Drumm Streets, California & Hyde Streets, California Street & Van Ness Avenue, and Hyde & Pacific Streets.

Project Phase (select dropdown be	elow)						
Construction (CON)							
Map or Drawings Attached?	Yes						
Other Items Attached?	Yes						
5YPP/STRATEGIC PLAN INFOR	RMATION						
Type of Project in the Prop K 5YPP/Prop AA Strategic Plan?	Project Drawn From Placeholder						
Is the requested amount greater than the amount programmed in the relevant 5YPP or Strategic Plan?	ed in Less than or Equal to Programmed Amount tegic						
Prop K 5YPP Amount:	Prop AA \$ 1,404,000 Strategic Plan Amount:						

# Locations of Cable Sheaves (large pulleys)

# for Cable Car System

# of Sheaves	Location	Associated Shutdown (Cable Car Gearbox Overhaul Project)	Dates
4	Cable Car Barn	1 w/ Powell, 1 w/ Mason 2 w/ Hyde	Powell April 2018, Mason Oct 2018, California and Hyde April 2019
80	Washington and Mason Streets	Scheduled with Hyde Line	April 2019
3	Powell and Washington Streets	Scheduled with Hyde Line	April 2019
2	Beach & Hyde Streets	Scheduled with Hyde Line	April 2019
2	California & Mason Streets	After Line service reduction No impact to service	Post June 2018
1	Bay & Taylor Streets	With Mason	October 2018
1	Powell & Market Streets	With Powell	April 2018
1	California & Drumm Streets	After Line service reduction No impact to service	Post June 2018
1	California & Hyde Streets	After Line service reduction No impact to service	Post June 2018
_	California Street & Van Ness Avenue	After Line service reduction No impact to service	Post June 2018
_	Hyde & Pacific Streets	After Line service reduction No impact to service	Post June 2018: Will occur on a scheduled Hyde Cable Replacement in late 2018.
25	Total		

Project Name: Cable Car Pulley Rebuild

### **ENVIRONMENTAL CLEARANCE**

**Environmental Type**: N/A

### PROJECT DELIVERY MILESTONES

Enter dates below for ALL project phases, not just for the current request, based on the best information available. For PLANNING requests, please only enter the schedule information for the PLANNING phase.

Phase	S	tart	End		
Filase	Quarter	Calendar Year	Quarter	Calendar Year	
Planning/Conceptual Engineering (PLAN)					
Environmental Studies (PA&ED)					
Right-of-Way					
Design Engineering (PS&E)					
Advertise Construction					
Start Construction (e.g. Award Contract)	Jan-Mar	2018			
Operations (i.e., paratransit)					
Open for Use			Jul-Sep	2020	
Project Completion (means last eligible expenditure)			Jul-Sep	2020	

### SCHEDULE DETAILS

Provide dates for any COMMUNITY OUTREACH planned during the requested phase(s). Identify PROJECT COORDINATION with other projects in the area (e.g. paving, MUNI Forward) and relevant milestone dates (e.g. design needs to be done by DATE to meet paving schedule). List any timely use-of-funds deadlines (e.g. federal obligation deadline). If a project is comprised of MULTIPLE SUB-PROJECTS, provide milestones for each sub-project. For PLANNING EFFORTS, provide start/end dates for each task.

The SFMTA plans to coordinate this project with the concurrent project to overhaul the cable car gearboxes. The overhaul of the gearboxes requires shutdowns of individual cable car lines. Implementation of that project is anticipated 2017-2021, and has already started with the shutdown of the California cable car line. See the attached shutdown schedule accommodating both the pulley and gearbox rebuild projects, coordinated to minimize impacts to the public.

Project Name: Cable Car Pulley Rebuild

### FUNDING PLAN - FOR CURRENT REQUEST

Enter the funding plan for the phase(s) that are the subject of the CURRENT REQUEST. Totals should match those shown in the Cost Summary below.

Fund Source	Pla	nned	Programmed		Allocated		Total
Prop K	\$	-	\$	280,999	\$	-	\$ 280,999
Prop AA	\$	-	\$	-	\$	-	\$ -
MTC AB664 Bridge Tolls	\$	-	\$	-	\$	136,000	\$ 136,000
FTA Formula Funds FY16	\$	-	\$	-	\$	263,001	\$ 263,001
SFMTA Operating funds	\$	-	\$	ı	\$	943,500	\$ 943,500
Total:	\$	-	\$	280,999	\$	1,342,501	\$ 1,623,500

### **COST SUMMARY**

Show total cost for ALL project phases (in year of expenditure dollars) based on best available information. Source of cost estimate (e.g. 35% design, vendor quote) is intended to help gauge the quality of the cost estimate, which should improve in reliability the farther along a project is in its development.

Phase	To	otal Cost	(	Prop K - Current Request	Prop AA - Current Request	Source of Cost Estimate
Planning/Conceptual Engineering (PLAN)	\$	-	\$	-		
Environmental Studies (PA&ED)	\$	-	\$	-		
Right-of-Way	\$	-	\$	-		
Design Engineering (PS&E)	\$	-	\$	-	\$ -	
Construction (CON)	\$	1,623,500	\$	280,999	\$ -	Estimate based on vendor quotes
Operations (Paratransit)	\$	-	\$	-		
Total:	\$	1,623,500	\$	280,999	\$ -	

% Complete of Design: 100% as of 10/25/2017
Expected Useful Life: 30 Years

### PROPOSED REIMBURSEMENT SCHEDULE FOR CURRENT REQUEST (instructions as noted below)

Use the table below to enter the proposed reimbursement schedule for the current request. Prop K and Prop AA policy assume these funds will not be reimbursed at a rate greater than their proportional share of the funding plan for the relevant phase unless justification is provided for a more aggressive reimbursement rate. If the current request is for multiple phases, please provide separate reimbursement schedules by phase. If the proposed schedule exceeds the years available, please attach a file with the requested information.

Fund Source	FY	2017/18	FY	2018/19	FY	2019/20	FY	2020/21	FY	2021/22+	Total
Prop K	\$	26,654	\$	125,368	\$	80,157	\$	48,820	\$	-	\$ 280,999
Prop AA	\$	-	\$	-	\$		\$	-	\$		\$ -

Page 7 of 12

### **San Francisco County Transportation Authority** Prop K/Prop AA Allocation Request Form Project Name: Cable Car Pulley Rebuild

### MAJOR LINE ITEM BUDGET

Budget Line Item	Totals ts/Material	SFI	MTA Labor	Col	ntingency	Та	ask Totals
Task 1: Final Quotes & Procurement Labor		\$	60,474			\$	60,474
Task 2: Street Sheaves	\$ 847,537	\$	526,583			\$	1,374,120
Task 3: Tension Sheaves	\$ 45,741	\$	132,143			\$	177,884
Contingency				\$	11,021	\$	11,021
Sub Totals	\$ 893,278	\$	719,201	\$	11,021		
TOTAL PROJECT COST						\$	1,623,500

### **Budget Details for Labor Costs**

	No. of FTEs	Total No. of Hours	•	Burdened st/Hour	То	tal Cost
Final Quotes and Procurement						
Maintenance Machinist (7332)	1	40	\$	149.67	\$	5,987
Wire Rope Mechanic (7472)	1	40	\$	154.17	\$	6,167
Mechanical Shop and Equip Supt (7126)	1	80	\$	185.76	\$	14,861
Maintenance Machinist Sup I (7258)	1	90	\$	185.47	\$	16,692
Engineer (5241)	1	16	\$	227.13	\$	3,634
Automotive Machinist (7313)	1	80	\$	146.96	\$	11,757
Wire Rope Mechanic Sup I (7286)	1	8	\$	172.10	\$	1,377
Total Quotes:					\$	60,474
Street Sheaves						
Mainteance Machinist (7332)	1	683	\$	149.67	\$	102,225
General Laborer (7514)	1	450	\$	114.88	\$	51,696
Wire Rope Mechanic (7472)	1	643	\$	154.17	\$	99,131
Mechanical Shop and Equip Supt (7126)	1	437	\$	185.76	\$	81,177
Maintenance Machinist Sup I (7258)	1	320	\$	185.47	\$	59,350
Engineer (5241)	1	8	\$	227.13	\$	1,817
Automotive Machinist (7313)	1	305	\$	146.96	\$	44,823
Wire Rope Mechanic Sup I (7286)	1	29	\$	172.10	\$	4,991
Welder (7390)	1	233	\$	151.13	\$	35,213
Track Maintenance Worker (7540)	1	395	\$	116.86	\$	46,160
Total Street Sheaves:					\$	526,583
Tension Sheaves						
Mainteance Machinist (7332)	1	280	\$	149.67	\$	41,908
General Laborer (7514)	1	48	\$	114.88	\$	5,514
Wire Rope Mechanic (7472)	1	120	\$	154.17	\$	18,500
Mechanical Shop and Equip Supt (7126)	1	88	\$	185.76	\$	16,347
Maintenance Machinist Sup I (7258)	1	120	\$	185.47	\$	22,256
Engineer (5241)	1	4	\$	227.13	\$	909
Automotive Machinist (7313)	1	120	\$	146.96	\$	17,635
Wire Rope Mechanic Sup I (7286)	1	8	\$	172.10	\$	1,377
Welder (7390)	1	20	\$	151.13	\$	3,023
Track Maintenance Worker (7540)	1	40	\$	116.86	\$	4,674
Total Tension Sheaves:					\$	132,143
Total Labor:					\$	719,201

·				
Parts/ Materials				
Street Sheaves				
Part Description	Qty	Co	st per unit	Total cost
Lower Bearing Cup	23	\$	462	\$ 10,620
Lower Bearing Cone	23	\$	622	\$ 14,299
Upper Bearing Cone	23	\$	2,561	\$ 58,905
Upper Bearing Cup	23	\$	2,743	\$ 63,088
Upper Bearing Spacer	27	\$	245	\$ 6,604
Seal Buna Oring small	31	\$	0	\$ 9
Seal Buna Oring Large	31	\$	5	\$ 155
Forsheda Seal	27	\$	139	\$ 3,756
Oil Tank	24	\$	317	\$ 7,620
Drain Kit	26	\$	247	\$ 6,427
Plumbing	26	\$	500	\$ 13,000
Breather	23	\$	22	\$ 495
Hardware	26	\$	400	\$ 10,400
Oil	550	\$	44	\$ 24,453
Water Finder	48	\$	130	\$ 6,240
Retainer Plate #2	22	\$	2,088	\$ 45,931
Bearing Clamp #3	22	\$	1,463	\$ 32,176
Bearing Retainer #5	22	\$	2,124	\$ 46,736
Lagging	3,628	\$	22	\$ 81,303
Seal Ring #8	26	\$	1,676	\$ 43,572
Shaft Machined Spindel #1	24	\$	3,650	\$ 87,600
Hardware Kit	26	\$	500	\$ 13,000
Pedastal #4	8	\$	33,889	\$ 271,148
Subtotal		Ť	,	\$ 847,537
Tension Sheaves				
Lagging	772	\$	22	\$ 17,301
Capstan	5	\$	4,250	\$ 21,250
Locking device at capstan	6	\$	265	\$ 1,590
Pillow Block Bearing	10	\$	-	\$ -
Sheave lock device	5	\$	550	\$ 2,750
Shaft	5	\$	-	\$ -
Electrical upgrade Cord Reel	8	\$	_	\$ -
Electrical Conduit	4	\$	150	\$ 600
Monitoring Install Misc	5	\$	450	\$ 2,250
Subtotal	-	*		\$ 45,741
Total Materials				\$ 893,278

### TRANSPORTATION AUTHORITY RECOMMENDATION

This se	ection is to be	e completed	by Transport	ation Authority Staff.						
Last Updated:	2/13/2018	Res. No:		Res. Date:						
Project Name:	Cable Car Pu	Illey Rebuild								
<b>Grant Recipient:</b>	Grant Recipient: San Francisco Municipal Transportation Agency - MUNI									
	Action	Amount	Pha	ase						
Funding	Prop K Allocation	\$ 280,999	Construction (0	CON)						
Funding Recommended:										
	Total:									
Total Prop K Funds: \$\frac{\$ 280,999}{} Total Prop AA Funds: \$\frac{\$}{}\$										
recommendations and notes for multi-sponsor recommendations:  Fund Expiration Date: 9/30/2021 Eligible expenses must be incurred prior to this date.										
Intended Future	Action	Amount	Fiscal Year	Phase						
Action										
Trigger:										
Deliverables:										
<ol> <li>Over the course of the project quarterly progress reports should include 2-3 photos of work in progress and completed work.</li> </ol>										
2. Quarterly progress reports should include the dates of the next										
3.										
4.										
<u>-</u>	Conditions:	not incur expe	enses for the c	construction phase until						
	Transportatio	n Authority st ipt of evidence	aff releases th	e funds (\$280,999) n of design (e.g. copy of						
2.		erhead multipl		mburse SFMTA up to the fiscal year that SFMTA						
3.										

### TRANSPORTATION AUTHORITY RECOMMENDATION

# This section is to be completed by Transportation Authority Staff. Last Updated: 2/13/2018 Res. No: Res. Date: Project Name: Cable Car Pulley Rebuild Grant Recipient: San Francisco Municipal Transportation Agency - MUNI Notes: 1. 2. Metric Prop K Prop AA Actual Leveraging - Current Request 82.69% No Prop AA

	110011	1100701
Actual Leveraging - Current Request	82.69%	No Prop AA
Actual Leveraging - This Project	See Above	See Above

**SFCTA Project** 

Reviewer: P&PD

### SGA PROJECT NUMBER

Sponsor: San Francisco Municipal Transportation Agency - MUNI

SGA Project Number: 122-910xxx Name: Cable Car Pulley Rebuild

 Phase:
 Construction (CON)
 Fund Share:
 17.31%

 Cash Flow Distribution Schedule by Fiscal Year

 Fund Source
 FY 2017/18
 FY 2018/19
 FY 2019/20
 FY 2020/21
 FY 2021/22+
 Total

 Prop K
 \$26,654
 \$125,368
 \$80,157
 \$48,820
 \$280,999

FY of Allocation Action: 2017/18 Current Prop K Request: \$ 289,999

Current Prop AA Request: \$

Project Name: Cable Car Pulley Rebuild

Grant Recipient: San Francisco Municipal Transportation Agency - MUNI

1) The requested sales tax and/or vehicle registration fee revenues will be used to supplement and under no circumstance replace existing local revenues used for transportation purposes.

### Required for Allocation Request Form Submission

Initials of sponsor staff member verifying the above statement

### $\mathsf{TM}$

	CONTACT	INFORMATION
	Project Manager	Grants Section Contact
Name:	Robert Bergesen	Tim Manglicmot
Title:	Project Manager	CPM, Acting Manager
Phone:	415.646.2146	415.646-2517
Email:	Robert.Bergesen@sfmta.com	timothy.manglicmot@sfmta.com







FY of Allocation Action: 2017/18

**Project Name:** 19th Avenue Complete Streets

**Grant Recipient:** San Francisco Municipal Transportation Agency - DPT

### **EXPENDITURE PLAN INFORMATION**

**Prop K EP category:** Upgrades to major arterials (including 19th Avenue): (EP-30)

Prop K EP Line Number (Primary): 30 Prop K Other EP Line Numbers:

Current Prop K Request: \$

425,000

Prop AA Category:

Current Prop AA Request: \$

Supervisorial District(s): District 04, District 07

### REQUEST

### **Brief Project Description (type below)**

Part of the 19th Avenue Combined City Project, the 19th Avenue Complete Streets project will construct 21 transit bulbs and 45 pedestrian bulbs between Lincoln Way and Holloway Avenue. The project will improve pedestrian safety and transit reliability and performance on this Vision Zero High Injury Corridor. The construction contract includes new signals at the intersections of 19th Avenue and Moraga, Wawona, Sloat, and Winston (previously funded by Prop K), and SFPUC sewer and water infrastructure upgrades. Caltrans will repave 19th Avenue after the Combined City Project work is done.

### **Detailed Scope, Project Benefits and Community Outreach (type below)**

Part of the 19th Avenue Combined City Project, the 19th Avenue Complete Streets Project will construct 21 transit bulbs and 45 pedestrian bulbouts on 19th Avenue between Lincoln Way and Holloway Avenue. Each of these intersections will be upgraded to meet standards set in the Federal Highway Administration's Manual on Uniform Traffic Control Devises (MUTCD), the Americans with Disabilities Act (ADA) and city ordinances. These upgrades will improve pedestrian safety at these intersections, as well as transit performance along this corridor.

Outreach was conducted to the community in 2015 in preparation for MTA Board legislation of the traffic and parking changes. Additional implementation phase outreach is planned to begin before notice to proceed is issued to the contractor to inform the community of upcoming construction and ensure they are aware of any impacts.

This project will be completed in coordination with the 19th Avenue Signals Phase III Project, as well as sewer and water infrastructure upgrades funded by SFPUC. The construction contract includes new signals at the intersections of 19th Avenue and Moraga, Wawona, Sloat, and Winston (funded by a prior Prop K allocation). Caltrans will repave the entire length of the 19th Avenue corridor using state funds after the City's complete streets work is done.

E7-14

### San Francisco County Transportation Authority Prop K/Prop AA Allocation Request Form

### Need:

19th Avenue is on the 2017 Vision Zero High Injury Network, and is one of Muni's busiest corridors - the 28/28R 19th Ave carry about 15,000 customers everyday. Transit and pedestrian improvements will be constructed in an effort to address vehicular, transit and pedestrian safety concerns throughout the corridor. This project will also improve transit service reliability and enhance the customer experience on and off the bus.

### Implementation:

Caltrans is the lead agency on the environmental documentation and has completed an independent Project Study Report. The Muni Forward and Vision Zero changes were covered by the Transit Effectiveness Project (TEP) environmental document certifed in March 2014. All contract work is being administered by Public Works.

roject Location (type below)
9th Avenue between Lincoln Way and Holloway Avenue
roject Phase (select dropdown below)
Construction (CON)
Map or Drawings Attached? Yes
Other Items Attached? No
YPP/STRATEGIC PLAN INFORMATION
Type of Project in the Prop K  Named Project  5YPP/Prop AA Strategic Plan?
Is the requested amount greater than the amount programmed in the relevant 5YPP or Strategic Plan?
Prop AA Prop K 5YPP Amount: \$ 425,000 Strategic Plan Amount:

#	Intersections	Improvement Locations
1	19th/Lincoln:	SW corner transit bulbout into 19th
2	19th/Irving:	NE comer pedestrian bulbout into 19th, NE corner pedestrian bulb into Irving, SW corner pedestrian bulbout into 19th, SW corner bulbout into Irving
က	19th/Judah:	NE corner transit bulbout into 19th, SW corner transit bulbout into 19th
4	19th/Kirkham:	NE corner pedestrian bulbout into 19th, NE corner pedestrian bulbout into Kirkham, SW corner pedestrian bulbout into 19th, SW corner pedestrian bulbout into Kirkham
5	19th/Lawton:	NE comer transit bulbout into 19th, NE corner pedestrian bulbout into Lawton, SE corner transit bulbout into 19th, SE corner pedestrian bulbout into Lawton
9	19th/Moraga:	NE comer pedestrian bulbout into 19th, NE corner pedestrian bulbout into Moraga, SE comer pedestrian bulbout into 19th
7	19th/Noriega:	NE comer transit bulbout into 19th, NE corner pedestrian bulbout into Noriega, SE comer transit bulbout into 19th
8	19th/Ortega:	NE comer transit bulbout into 19th, NE corner pedestrian bulbout into Ortega, SW comer transit bulbout into 19th, SW corner pedestrian bulbout into Ortega
6	19th/Pacheco:	NE corner pedestrian bulbout into 19th, NE corner pedestrian bulbout into Pacheco, SW corner pedestrian bulbout into Pacheco
10	19th/Quintara:	NE comer pedestrian bulbout into 19th, NE corner pedestrian bulbout into Quintara, SW corner transit bulbout into 19th, SW corner pedestrian bulbout into Quintara
1	19th/Rivera:	NE comer transit bulbout into 19th, NE corner pedestrian bulbout into Rivera, SW corner transit bulbout into 19th, SW corner pedestrian bulbout into Rivera
12	19th/Santiago:	NE comer pedestrian bulbout into 19th, NE corner pedestrian bulbout into Santiago, SW corner pedestrian bulbout into Santiago
13	19th/Taraval:	NE corner transit bulbout into 19th, SW corner transit bulbout into 19th
14	19th/Ulloa:	NE comer pedestrian bulbout into 19th, NE corner pedestrian bulbout into Ulloa, SW corner pedestrian bulbout into Ulloa
15	19th/Vicente:	NE corner transit bulbout into 19th, NE corner pedestrian bulbout into Vicente, SW corner transit bulbout into 19th, SW corner pedestrian bulbout into Vicente
16	19th/Wawona:	NE comer pedestrian bulbout into 19th, SE corner pedestrian bulbout into 19th
17	19th/Sloat:	NE corner transit bulbout into 19th, SE corner pedestrian bulbout into Sloat, NW corner pedestrian bulbout into Sloat, SW corner transit bulbout into 19th, SW corner pedestrian bulbout into Sloat
18	19th/Eucalyptus:	NE corner transit bulbout into 19th, NE corner pedestrian bulbout into Eucalyptus, SW corner transit bulbout into 19th, SW corner pedestrian bulbout into Eucalyptus
19	19th/Holloway:	NE corner transit bulbout, SE corner pedestrian bulbout into 19th, SE corner pedestrian bulbout into Holloway

Total transit bulbs: 21 Total pedestrian bulbs: 45

Project Name: 19th Avenue Complete Streets

### **ENVIRONMENTAL CLEARANCE**

**Environmental Type:** EIR/EIS

### PROJECT DELIVERY MILESTONES

Enter dates below for ALL project phases, not just for the current request, based on the best information available. For PLANNING requests, please only enter the schedule information for the PLANNING phase.

Phase	St	art	E	nd
Filase	Quarter	Calendar Year	Quarter	Calendar Year
Planning/Conceptual Engineering (PLAN)	Jul-Sep	2011	Apr-Jun	2015
Environmental Studies (PA&ED)	Jul-Sep	2011	Apr-Jun	2015
Right-of-Way				
Design Engineering (PS&E)				
Advertise Construction	Jan-Mar	2018		
Start Construction (e.g. Award Contract)	Jul-Sep	2018		
Operations (i.e., paratransit)				
Open for Use			Jul-Sep	2020
Project Completion (means last eligible expenditure)			Jan-Mar	2021

### SCHEDULE DETAILS

Provide dates for any COMMUNITY OUTREACH planned during the requested phase(s). Identify PROJECT COORDINATION with other projects in the area (e.g. paving, MUNI Forward) and relevant milestone dates (e.g. design needs to be done by DATE to meet paving schedule). List any timely use-of-funds deadlines (e.g. federal obligation deadline). If a project is comprised of MULTIPLE SUB-PROJECTS, provide milestones for each sub-project. For PLANNING EFFORTS, provide start/end dates for each task.

SFMTA will work with Public Information Officers from SFMTA and DPW to be main contact points to stakeholders and respond to any construction related questions or direct constituents to the project website for information. Additionally, SFMTA's outreach team has created a draft plan to re-activate communications for this project since SFMTA Board legislation was over a year ago at this point.

19th Avenue Complete Streets Project must finish construction before Caltrans' street resurfacing. The Caltrans street resurfacing project is programmed in the SHOPP for FY 17/18 with advertisement in Q4, FY 18/19. Construction will be completed in segments. This allows the 19th Ave Complete Streets project to finish later segments while Caltrans begins earlier segments. Note: The City is currently awaiting Caltrans approvals before construction can begin.

Milestone (complete streets project only)	Completion Date:
Final SFMTA Transit Improvement Program EIR	March 2014
Draft Project Study Report (PSR) & Fact Sheets	February 2015
Final CEQA Documentation by Caltrans	May 2015
Final Project Study Report by Caltrans	May 2015
Begin Design	July 2015
Construction Contract Advertisement	March 2018
Construction Contract Award	September 2018
End Construction	August 2020

Additional work in the project area include work at 19th/Rossmoor, which is being constructed through the M-Line track replacement project. The construction on this location is May 1, 2017 - August 7, 2019. Additionally, Caltrans is responsible for signal upgrades, as part of their resurfacing contract, at four locations on 19th Avenue: Park Presidio/Lake, Crossover/Park Presidio, Crossover/MLK, 19th/Sloat. Construction will occur from Summer 2020 to Summer 2021.

Project Name: 19th Avenue Complete Streets

### FUNDING PLAN - FOR CURRENT REQUEST

Enter the funding plan for the phase(s) that are the subject of the CURRENT REQUEST. Totals should match those shown in the Cost Summary below.

Fund Source	Planned	Programmed	Allocated	Total
Prop K	\$ -	\$ 425,000	\$ 1,399,608	\$ 1,824,608
Prop AA	\$ -	\$ -	\$ -	\$ -
Prop A GO Bonds	\$ -	\$ 16,641,392	\$ -	\$ 16,641,392
	\$ -	\$ -	\$ -	\$ -
Total:	\$ -	\$ 17,066,392	\$ 1,399,608	\$ 18,466,000

### FUNDING PLAN - FOR ENTIRE PROJECT (ALL PHASES)

Enter the funding plan for all phases (planning through construction) of the project. This section may be left blank if the current request covers all project phases. Totals should match those shown in the Cost Summary below.

Fund Source	Planned	Programmed	Allocated	Total
Prop K	\$ -	\$ 425,000	\$ 1,839,608	\$ 2,264,608
Prop AA	\$ -	\$ -	\$ -	\$ -
Prop A GO Bonds	\$ -	\$ 16,641,392	\$ -	\$ 16,641,392
	\$ -	\$ -	\$ -	\$ -
Total:	\$ -	\$ 17,066,392	\$ 1,839,608	\$ 18,906,000

### **COST SUMMARY**

Show total cost for ALL project phases (in year of expenditure dollars) based on best available information. Source of cost estimate (e.g. 35% design, vendor quote) is intended to help gauge the quality of the cost estimate, which should improve in reliability the farther along a project is in its development.

Phase	Total Cost	Prop K - Current Request	Prop AA - Current Request	Source of Cost Estimate
Planning/Conceptual Engineering (PLAN)	\$ -	\$ -		
Environmental Studies (PA&ED)	\$ -	\$ -		
Right-of-Way	\$ -	\$ -		
Design Engineering (PS&E)	\$ 440,000	\$ -	\$ -	Actual Cost
Construction (CON)	\$ 18,466,000	\$ 425,000	\$ -	Engineer's Estimate at 95% design
Operations (Paratransit)	\$ -	\$ -		
Total:	\$ 18,906,000	\$ 425,000	\$ -	

% Complete of Design:	95%	as of	1/25/2018
<b>Expected Useful Life:</b>	30	Years	

### PROPOSED REIMBURSEMENT SCHEDULE FOR CURRENT REQUEST (instructions as noted below)

Use the table below to enter the proposed reimbursement schedule for the current request. Prop K and Prop AA policy assume these funds will not be reimbursed at a rate greater than their proportional share of the funding plan for the relevant phase unless justification is provided for a more aggressive reimbursement rate. If the current request is for multiple phases, please provide separate reimbursement schedules by phase. If the proposed schedule exceeds the years available, please attach a file with the requested information.

Fund Source	FY	2017/18	FY	2018/19	FY	2019/20	FY 2	2020/21	FY 2	2021/22+	Total
Prop K	\$	-	\$	425,000	\$	-	\$	-	\$	-	\$ 425,000
Prop AA	\$	-	\$	-	\$	1	\$	-	\$	-	\$ -

# Project Name: 19th Avenue Complete Streets

# **MAJOR LINE ITEM BUDGE**

### CONSTRUCTION

SUMMARY BY MAJOR LINE ITEM (BY AGENCY LABOR B	OR BY TASK)					
Budget Line Item	Totals	% of contract	MddS	SFMTA		Contractor
19th Avenue Complete Streets Project						
1. Contract						
Task 1: Civil Improvements (Transit and Ped Bulbs)	\$ 4,160,000				\$	4,160,000
Task 2: Electrical Improvements	1,507,000				\$	1,507,000
Task 3: Sewer Relocations (triggered) <sup>1</sup>	\$ 799,000				\$	799,000
Task 4: Water Relocations (triggered) <sup>1</sup>	\$ 804,000				\$	804,000
Task 5: AWSS Relocations (triggered) <sup>1</sup>	1,594,000				S	1,594,000
Task 6: Shared Costs (Traffic Routing, Mobilization, etc)	1,325,000				\$	1,325,000
Contract Subtotal	\$ 10,189,000				\$	10,189,000
2. Equipment Procurement	\$ 100,000	4%		\$ 100,000	00	
3. Permits and Fees	\$ 120,000	1%	\$ 120,000			
4. SFMTA Shop Support	\$ 800,000	%8		000'008 \$	00	
5. Construction Management/Engineering	3,567,000	%98	3,567,000			
6. Outreach (SFMTA and PW)	\$ 632,500	%9	\$ 202,500	430,000	00	
6. Contingency*	3,057,000	%0E	1,019,000	2,038,000	00	
TOTAL CONSTRUCTION PHASE	\$ 18,465,500		\$ 4,908,500	3,368,000	\$ 00	20,378,000

City Attorney Fees	\$ 200
Phase Grand Total	\$ 18,466,000

<sup>\* 10%</sup> contingency + 20% allowance for high bid prices due to saturated construction market

<sup>&</sup>lt;sup>1</sup> Triggered means these facilities will need to be relocated as a result of the bulbout construction for this project. The amount indicated is how much the SFMTA is responsible for contributing for this work.

	TRANSPORTATION AUTHORITY RECOMMENDATION  This section is to be completed by Transportation Authority Staff.							
		e completed	by Iransport					
Last Updated:	2/23/2018	Res. No:		Res. Date:				
Project Name:	19th Avenue	Complete Stre	eets					
<b>Grant Recipient:</b>	San Francisc	o Municipal T	ransportation A	Agency - DPT				
	Action	Amount	Pha	ase				
	Prop K Allocation	\$ 425,000	Construction (0	CON)				
Funding Recommended:								
Necommended.								
	Total:	\$ 425,000						
Total Prop K Funds: \$\\\ \$ 425,000  Total Prop AA Funds:								
Justification for multi-phase recommendations and notes for multi-sponsor recommendations:								
Fund Expira	ation Date:	9/30/2021	Eligible experto this date.	ses must be incurred prior				
Intended Future	Action	Amount	Fiscal Year	Phase				
Action								
Trigger:								
Ji.	Quarterly progress reports shall provide the schedule for work to be performed in the upcoming quarter, an overview of the work performed in the preceeding quarter, percent complete for each location, and the percent complete for the overall project, in addition to all other requirements described in the Standard Grant Agreement (SGA). Over the course of the project quarterly progress reports should include 2-3 photos of work in progress for recent activities and/or of completed work. See SGA for definitions.							
3.	(anticipated S schedule by s Provide the T following Calt	September 20 segment. raffic Manage trans approva	18) , provide the ement Plan and l.	ng contract award ne final construction d Public Information Plan , provide copies of the				
Snoois	I Conditions:							
			enses for the c	onstruction phase until				
	Transportatio	n Authority sta	aff releases th	e funds (\$425,000)				
	certifications	page).	•	n of design (e.g. copy of				
2.				mburse SFMTA up to the fiscal year that SFMTA				

3.

### TRANSPORTATION AUTHORITY RECOMMENDATION

This section is to be completed by Transportation Authority Staff.

Last Updated: 2/23/2018 Res. No: Res. Date: Project Name: 19th Avenue Complete Streets

Grant Recipient: San Francisco Municipal Transportation Agency - DPT

### Notes:

1. At the February 13 Board meeting, Chair Peskin asked staff to prepare a presentation on traffic mitigation and outreach plans related to a series of major construction projects on several of the city's key arterials that are anticipated to have overlapping schedules. These include projects on 19th Avenue (including the subject project), Lombard, Van Ness and Geary. We anticipate a presentation on this topic at the March 20 Board meeting.

Metric	Prop K	Prop AA
Actual Leveraging - Current Request	90.12%	No Prop AA
Actual Leveraging - This Project	88.02%	No Prop AA

SFCTA Project P&PD Reviewer:

### SGA PROJECT NUMBER

Sponsor: San Francisco Municipal Transportation Agency - DPT

SGA Project Number: 133-907xxx Name: 19th Avenue Complete Streets

 Phase:
 Construction (CON)
 Fund Share:
 9.88%

 Cash Flow Distribution Schedule by Fiscal Year

 Fund Source
 FY 2017/18
 FY 2018/19
 FY 2019/20
 FY 2020/21
 FY 2021/22+
 Total

 Prop K
 \$170,000
 \$170,000
 \$85,000
 \$425,000

Project Name: 19th Avenue Complete Streets

Grant Recipient: San Francisco Municipal Transportation Agency - DPT

1) The requested sales tax and/or vehicle registration fee revenues will be used to supplement and under no circumstance replace existing local revenues used for transportation purposes.

### Required for Allocation Request Form Submission


Initials of sponsor staff member verifying the above statement

### $\mathsf{TM}$

	CONTACT INFO	RMATION
	Project Manager	Grants Section Contact
Name:	Manito Velasco	Timothy Manglicmot
Title:	Senior Engineer	Principal Administrative Analyst
Phone:	(415) 701-4447	(415) 646-2517
Email:	Manito.Velasco@sfmta.com	Timiothy.Manglicmot@sfmta.com

### MAPS AND DRAWINGS

19th Avenue Complete Streets





**This Page Intentionally Left Blank** 

5.289.722

### San Francisco County Transportation Authority Prop K/Prop AA Allocation Request Form

FY of Al	location <i>i</i>	Action:	2017/18

**Project Name:** New Traffic Signals Contract 64

Grant Recipient: San Francisco Municipal Transportation Agency - DPT

### **EXPENDITURE PLAN INFORMATION**

**Prop K EP category:** New Signals and Signs: (EP-31)

Prop K EP Line Number (Primary): 31 Current Prop K Request: \$

Prop K Other EP Line Numbers:

Prop AA Category:

Current Prop AA Request: \$

Supervisorial District(s): District 03, District 05, District 06, District 08, District 09, District 10,

### REQUEST

### **Brief Project Description (type below)**

Construction of new traffic signals at nine intersections to improve traffic, pedestrian, and bicycle safety. The scope of work includes new traffic signals (mast arms, signal heads, controllers, conduit, wiring, and poles), pedestrian countdown signals, accessible (audible) pedestrian signals, and curb ramps.

### Detailed Scope, Project Benefits and Community Outreach (type below)

See Attached

### **Project Location (type below)**

- 1) Bryant Street/Sterling Street
- 2) 7th Street/Minna Street
- 3) Mariposa Street/Pennsylvania Avenue
- 4) Ellis Street/Webster Street
- 5) Mission Street/Highland Avenue
- 6) Owens Street/Campus Way
- 7) 15th Street/Dolores Street
- 8) Alemany Boulevard/Foote Avenue
- 9) Leavenworth Street/Washington Street

### Project Phase (select dropdown below)

Construction (CON)

Map or Drawings Attached? Yes

Other Items Attached? Yes

### 5YPP/STRATEGIC PLAN INFORMATION

Type of Project in the Prop K New Project 5YPP/Prop AA Strategic Plan?	
5YPP/Prop AA Strategic Plan?	

### Please describe and justify the necessary amendment:

The SFMTA is requesting a Prop K Strategic Plan amendment to advance a total of \$3,571,249 in the New Signals and Signs category from outyears of the Prop K program to FY 2017/18. See attached Strategic Plan amendment for details.

The SFMTA is also requesting a concurrent New Signals and Signs 5YPP amendment to add the subject project and to reprogram a total of \$1,718,473 to fully fund the subject request from the following projects that have already advanced or will advance with non-Prop K sources (e.g. SFMTA revenue bonds, Prop B General Fund setaside): \$200,000 from New Equipment, \$150,000 from Follow-the-Paving (New Pavement Markers and Conduits), \$200,000 from New Pavement Markers, \$868,473 from New Pedestrian Countdown Signals, and \$300,000 from New Traffic Signs.

### Scope

The San Francisco Municipal Transportation Agency (SFMTA) is requesting Prop K funds for the construction of nine new signalized intersections as part of the Contract 64 New Traffic Signals Project. All new signal locations will have new pedestrian countdown signals (PCS), accessible pedestrian signals (APS), controllers, conduit, wiring, poles, and curb ramps.

The locations under this project are as follows:

#	Intersection	Pedestrian Improvements	Existing Control	District	Vision Zero Location	Walk First	Muni Lines
1	Bryant St & Sterling St	PCS, APS, Ramps, 3 mast arms	None	6			
2	7th St & Minna St	PCS, APS, Ramps, 1 mast arm	1-way Stop	6			19
3	Mariposa St & Pennsylvania Ave	PCS, APS, Ramps, 2 mast arms	2-way Stop	10			
4	Ellis St & Webster St	PCS, APS, 2 mast arms	All-way Stop	5	X	X	
5	Mission St & Highland Ave	PCS, APS, 2 mast arms	2-way Stop	8,9			14, 14R, 49
6	Owens St & Campus Way	PCS, APS, Ramps, 2 mast arms	None	6			
7	15th St & Dolores St	PCS, APS	All-Way Stop	8	X		
8	Alemany Blvd & Foote Ave	PCS, APS, Ramps, 2 mast arms	2-way Stop	11	X	X	
9	Leavenworth St & Washington St	PCS, APS, Ramps	2-way Stop	3			27, Cable Car

### **Cost:**

As of January 2017 the project budget for the design and construction phases of New Signals Contract 64 was \$3,600,000 (or about \$400,000 per signal). The updated project cost estimate is \$6,554,040 (or about \$730,000 per signal). See Factors Affecting Current Bid Prices, below. All of the increase is in the construction phase, and SFMTA is therefore requesting \$5.3 million for construction rather than the \$2.9 million anticipated at the start of design.

### Implementation:

SFMTA's Sustainable Streets Division managed the scope of the detailed design. San Francisco Public Works' (SFPW's) Infrastructure Design and Construction (IDC) division will manage the issuance and administration of the contract for construction by competitively bid contract.

<u>Task</u> <u>Force Account Work Performed By</u>

Design
 SFMTA Sustainable Streets Division

Electrical Design
 Construction Management
 SFPW Infrastructure Design and Construction
 SFPW Infrastructure Construction Management

• Contract Support SFPW Bureau of Engineering

• Construction Support SFMTA Sustainable Streets Division

### Public Engagement

SFMTA secured public hearing approval for the nine new signals in Contract 64 on 8/19/2016. SFMTA received two comments about the Alemany/Foote signal as well a half-dozen concerns about the 15th Street/Dolores Signal, and SFMTA staff successfully addressed the concerns raised by the community at both intersections.

The Bryant/Sterling signal was requested by the community as part of a new building renovation at 340 Bryant Street. This intersection feeds the Sterling Street onramp onto the Bay Bridge. SFMTA staff met with the community along with Caltrans on 8/11/2015, and the consensus was to signalize this location. Caltrans supports the decision to signalize. SFMTA met with the neighbors and developer an additional 3 times in 2015 and 2016. WalkSF was also present at a meeting and provided their input.

### **Project Benefits**

New traffic signals provide the benefits of improved right-of-way assignment and access across major streets. Seven of the nine proposed signal locations currently have no controls or stop sign controls on the side street, while the major street is uncontrolled. Motorists from the side street have to stop and proceed only when there is a safe gap in traffic. Most importantly, pedestrians who cross the major street must also choose a gap in traffic in determining when to cross and depend on motorists to yield to them once they legally enter the crosswalk. New traffic signals will improve conditions for pedestrians by stopping traffic along the major street while allowing pedestrians and cross-traffic to proceed.

Two locations are existing all-way STOP locations. SFMTA recommends converting them to signals to maintain the pattern of similar traffic controls along a corridor. Moreover, these two locations involve wide multi-lane streets where right-of-way may be unclear to some motorists. The new signals will help to convey the appropriate right-of-way and ensure consistency of traffic controls on a corridor-wide basis.

All new traffic signals the SFMTA installs will have Pedestrian Countdown Signals (PCS). PCSs have been effective in reducing the number of pedestrians remaining in the crosswalk at the beginning of the conflicting vehicle green light, thereby reducing the potential for vehicle-pedestrian conflicts. The countdown feature of the PCS is helpful for pedestrians to discern as to whether there is enough time left in a signal cycle to cross the intersection safely. In addition, all new traffic signals will receive accessible pedestrian signals (APS) on all the corners to help the visually impaired receive pedestrian indications. Curb ramps will be upgraded to meet Americans with Disabilities Act standards where they currently do not, and additional street lighting will be installed as needed.

### **Project Location Selection Evaluation**

The intersections in this scope were selected after careful review by SFMTA staff of traffic signal requests received by the Agency each year, as well as locations nominated by staff. Locations are prioritized based on collision history, traffic volumes, benefits to roadway users including pedestrians, bicyclists, transit and motorists, proximity to schools or senior centers and any joint departmental opportunities (e.g. scheduled paving projects, corridor improvements).

All the locations proposed for signalization are intended to improve pedestrian safety on the City's primary and secondary arterial streets. SFMTA has developed a separate new signal contract which addresses intersections that are in the Walkfirst Pedestrian High-Injury Corridors. That separate project will be funded by Walkfirst funds, and is under construction as of December 2017.

The intersections in this subject request involve multi-lane streets like Webster Street, Dolores Street, Bryant Street, 7<sup>th</sup> Street, Mission Street, Owens Street, and Alemany Boulevard which are susceptible to the multiple-threat situation where a motorist may stop for a pedestrian or other cross street traffic but motorists in the adjacent lane may not. Speeds can also be a significant factor. Even streets with 25 MPH speed limits can be very intimidating for pedestrians to cross. At most of these locations, the SFMTA has installed continental crosswalks, advance signage, and other traffic control devices to highlight these pedestrian crossings. At this time, however, SFMTA staff believes signalization would improve the pedestrian right-of-way issues at these locations.

Bryant Street and Sterling Street is a location where the neighborhood has requested pedestrian crossing improvements next to a freeway on-ramp, in order to connect the north and south sides of Bryant Street with a controlled pedestrian crossing. Without the new signal, pedestrians would need to take a long detour to 2<sup>nd</sup> Street in order to cross at a controlled crosswalk. New crosswalks, signage, and a pedestrian island were installed in 2016 as an interim improvement in anticipation of a new signal. The private developer of 340 Bryant Street is providing \$200,318 towards a new signal.

A new signal at 7<sup>th</sup> Street and Minna Street will improve pedestrian conditions in a rapidly developing neighborhood, especially due the long blocks in the neighborhood and multi-lane uncontrolled 7<sup>th</sup> Street. The Eastern Neighborhoods Transportation Improvements Study recommends signalizing these types of alley intersections with 7<sup>th</sup> Street to improve pedestrian connectivity and to address pedestrian collisions on the 7<sup>th</sup> Street corridor. A new mixed-use commercial and housing development is also proposed at the northeast corner. SFMTA anticipates receiving \$210,000 towards the construction of this signal from the SOMA Stabilization Fund administered by the Mayor's Office.

Mission Street and Highland Avenue has a documented pedestrian collision history. Mission Street is a four-lane roadway with uncontrolled approaches and Muni bus zones at two corners. This location is an attractive pedestrian crossing between the Glen Park and Bernal Heights neighborhoods because the adjacent Highland Avenue Bridge over San Jose Avenue is one of only a few crossings across the Bernal Cut. SFMTA has received multiple requests for pedestrian safety improvements here.

Owen Street and Campus Way: With the opening of the new Mission Bay Circle and the full buildout of the Mission Bay neighborhood, it is expected that traffic volumes will drastically increase on Owens Street, making it more difficult for pedestrians to find gaps in traffic to cross Owens Street to travel between the buildings on the west side of Owens Street and the rest of the Mission Bay neighborhood. There are no controlled intersections to cross Owens Street for a 700 foot stretch, so Campus Way is a natural location for a signal since Campus Way funnels pedestrians through the neighborhood to cross Owens Street at the proposed signal.

Mariposa Street and Pennsylvania Avenue is located next to the on and off ramps to Interstate 280. A new development is being constructed on an adjacent parcel, and the developer has an agreement with the City to contribute \$154,000 toward construction of a new signal as part of the development's approval. Prop K will contribute the remaining portion. This new signal will complement the new signal being installed at the adjacent intersection of Mariposa Street and the I-280 on-ramp, and also improves pedestrian connections due to the increased pedestrian activity generated by the new development and the nearby Mission Bay neighborhood.

Ellis Street and Webster Street has a higher than average number of pedestrian collisions. As an interim measure to address the pedestrian safety issues here, SFMTA converted the intersection from a two-way STOP to an all-way STOP in 2016. However, SFMTA recommends upgrading this location to a signal to have consistent traffic controls along the signalized Webster Street Corridor. Moreover, SFMTA installed traffic signal conduits at this location in coordination with a SFPW paving contract on Webster Street in early 2017. The conduits were funded with \$150,000 in SFMTA funds.

15<sup>th</sup> Street and Dolores Street has a higher-than-average number of collisions, despite the fact that it is an all-way STOP intersection. The wide multi-lane nature of Dolores Street makes it more difficult for motorists and cyclists to determine who has the right-of-way when stopped at the STOP sign. Moreover, this is the only all-way STOP intersection along Dolores Street north of 21<sup>st</sup> Street. A new signal at 15<sup>th</sup> Street will improve the consistency of traffic controls along the corridor and address the high collision totals.

<u>Alemany Boulevard at Foote Avenue</u> is both a Vision Zero Location and a Walkfirst Location. Alemany Boulevard is a four-lane street with a 35 mile per hour speed limit. A signal will address documented pedestrian collisions and improve connections in the Outer Mission neighborhood.

Leavenworth Street and Washington Street is a location with a higher-than-average number of broadside vehicular collisions. This is a two-way STOP location with less-than ideal visibility due to an uphill approach. SFMTA has previously removed parking at the corners to improve sight lines and visibility, but the collision numbers have not shown noticeable improvement. An all-way STOP is not feasible here because Cable Cars approach this intersection on an uphill incline, and are unable to stop at a STOP sign at an uphill approach. On an uphill, Cable Cars must stay gripped to the constantly moving cable to propel the car forward and to prevent rolling downhill backwards. A signal will address the broadside collision pattern here and satisfy the unique needs of Cable Cars.

Table 3 - Prioritization Criteria and Scoring Table New Signals and Sign (EP 31)

	PROP K P	K PROGRAM-WIDE CRITERIA	CRITERIA	CATEGO	CATEGORY SPECIFIC CRITERIA	CRITERIA	
	Project Readiness	Community Support	Time Sensitive Urgency	Safety	Provides Benefits to Multiple Users	Supports Transit First	Total
Total Possible Score	4	3	3	4	3	3	20
New Equipment							
New Equipment	2	0	1	2	3	3	11
Follow-the-Paving							
Follow-the-Paving (New Pavement Markers and Conduits)		Locations will	Locations will be scored at the time of allocation. See text for more details.	of allocation. Se	e text for more de	etails.	
Traffic Signal Conduit Contract	4	1	3	3	2	1	14
New Traffic Signals							
New Traffic Signals Contract 62 [8 locations]	4	1	0	4	3	1	13
New Traffic Signals (5 Locations)		Locations will	Locations will be scored at the time of allocation. See text for more details.	of allocation. Se	e text for more de	etails.	
New Signal Contract 63 [11 locations]	4	2	0	4	3	1	14
New Traffic Signals Contract 64 [9 locations]	4	2	1	4	3	1	15
Safe Streets							
Active Transportation Program Local Match							
Safety Enhancements (New Pavement Markers)		Locations will	Locations will be scored at the time of allocation. See text for more details.	of allocation. Se	e text for more de	etails.	
New Pedestrian Countdown Signals New Traffic Signs							

# Prioritization Criteria Definitions:

current project status (e.g. expect more detail and certainty for a project about to enter construction than design); whether prior project phases are completed or expected to be Project Readiness: Project likely to need funding in fiscal year proposed. Factors to be considered include adequacy of scope, schedule, budget and funding plan relative to completed before beginning the next phase; and whether litigation, community opposition or other factors may significantly delay project.

Community Support: Project has clear and diverse community support and/or was it identified through a community-based planning process. An example of a community-Two points for a project with evidence of support from both neighborhood stakeholders and groups and citywide groups. based plan is a neighborhood transportation plan, but not a countywide plan or agency capital improvement program. Three points for a project in an adopted community based plan with evidence of diverse community support.

One point for a project with evidence of support from either neighborhood stakeholders and groups or citywide groups.

### Table 3 - Prioritization Criteria and Scoring Table New Signals and Sign (EP 31)

Time Sensitive Urgency: Project needs to proceed in proposed timeframe to enable construction coordination with another project (e.g., minimize costs and construction impacts); to support another funded or proposed project (e.g. new signal controllers need to be installed to support TEP implementation); or to meet timely use of funds deadlines associated with matching funds.

### New Equipment Subcategory:

Safety: Improves or mitigates a documented unsafe condition -- Improves worker safety.

Replaces asset at end of useful life: Replaces equipment that has reached the end of useful life per industry-accepted levels. Improves Project Delivery Rate: Supports accelerated project delivery (e.g., additional paint truck).

### All Other Subcategories:

Safety: (One point for each): Addresses demonstrated safety issue; reduces potential conflicts between modes; benefits users of multiple modes; and increases security.

Provides Benefits to Multiple Users: Projects receives one point each for addressing the needs of pedestrians, bicyclists, and/or transit users. Supports Transit First: Project improves transit service and reduces delay for transit vehicles at intersections controlled by traffic signals.

Project Name: New Traffic Signals Contract 64

### **ENVIRONMENTAL CLEARANCE**

**Environmental Type**: Categorically Exempt

### PROJECT DELIVERY MILESTONES

Enter dates below for ALL project phases, not just for the current request, based on the best information available. For PLANNING requests, please only enter the schedule information for the PLANNING phase.

Phase	St	art	End		
Filase	Quarter	Calendar Year	Quarter	Calendar Year	
Planning/Conceptual Engineering (PLAN)					
Environmental Studies (PA&ED)			Jan-Mar	2017	
Right-of-Way					
Design Engineering (PS&E)	Jan-Mar	2017	Jan-Mar	2018	
Advertise Construction	Apr-Jun	2018			
Start Construction (e.g. Award Contract)	Oct-Dec	2018			
Operations (i.e., paratransit)					
Open for Use			Oct-Dec	2019	
Project Completion (means last eligible expenditure)			Apr-Jun	2020	

### SCHEDULE DETAILS

Provide dates for any COMMUNITY OUTREACH planned during the requested phase(s). Identify PROJECT COORDINATION with other projects in the area (e.g. paving, MUNI Forward) and relevant milestone dates (e.g. design needs to be done by DATE to meet paving schedule). List any timely use-of-funds deadlines (e.g. federal obligation deadline). If a project is comprised of MULTIPLE SUB-PROJECTS, provide milestones for each sub-project. For PLANNING EFFORTS, provide start/end dates for each task.

Environmental clearance for 8 of 9 project locations was obtained on 11/22/2016 via a categorical exemption. These 8 locations were approved by the SFMTA Board on 1/18/2017. The remaining 15th Street/ Dolores Street location received a categorical exemption on 1/19/2017, and we received SFMTA Board approval on 3/7/2017.

The Highland/Mission location is being coordinated with Muni Forward efforts on Mission Street. The Ellis/Webster location had underground conduits installed as part of an ongoing repaving of Webster Street in 2017 to avoid breaking the 5-year paving moratorium.

Project Name: New Traffic Signals Contract 64

### FUNDING PLAN - FOR CURRENT REQUEST

Enter the funding plan for the phase(s) that are the subject of the CURRENT REQUEST. Totals should match those shown in the Cost Summary below.

Fund Source	ı	Planned	Pro	grammed	A	llocated	Total
Prop K	\$	5,289,722			\$	-	\$ 5,289,722
Prop AA	\$	-	\$	-	\$	-	\$ -
Private Developers	\$	-	\$	-	\$	354,318	\$ 354,318
SOMA Stabilization Fund	\$		\$		\$	210,000	\$ 210,000
Total:	\$	5,289,722	\$	-	\$	564,318	\$ 5,854,040

### FUNDING PLAN - FOR ENTIRE PROJECT (ALL PHASES)

Enter the funding plan for all phases (planning through construction) of the project. This section may be left blank if the current request covers all project phases. Totals should match those shown in the Cost Summary below.

Fund Source	ı	Planned	Pro	grammed	A	Allocated	Total
Prop K	\$	5,289,722	\$	-	\$	126,514	\$ 5,416,236
Prop AA	\$	-	\$	-	\$		\$ -
SFMTA Revenue Bond	\$	-	\$	-	\$	573,486	\$ 573,486
Private Developers	\$	-	\$	-	\$	354,318	\$ 354,318
SOMA Stabilization Fund	\$	-	\$	-	\$	210,000	\$ 210,000
Total:	\$	5,289,722	\$	-	\$	1,264,318	\$ 6,554,040

### **COST SUMMARY**

Show total cost for ALL project phases (in year of expenditure dollars) based on best available information. Source of cost estimate (e.g. 35% design, vendor quote) is intended to help gauge the quality of the cost estimate, which should improve in reliability the farther along a project is in its development.

Phase	Total Cost	Prop K - Current Request	Prop AA - Current Request	Source of Cost Estimate
Planning/Conceptual Engineering (PLAN)	\$ -	\$ -		
Environmental Studies (PA&ED)	\$ -	\$ -		
Right-of-Way	\$ -	\$ -		
Design Engineering (PS&E)	\$ 700,000		\$ -	Actual + cost to complete
Construction (CON)	\$ 5,854,040	\$ 5,289,722	\$ -	Recent SFMTA Signal Projects
Operations (Paratransit)	\$ -	\$ -		
Total:	\$ 6,554,040	\$ 5,289,722	\$ -	

% Complete of Design: 90% as of 1/12/2018
Expected Useful Life: 30 Years

### PROPOSED REIMBURSEMENT SCHEDULE FOR CURRENT REQUEST (instructions as noted below)

Use the table below to enter the proposed reimbursement schedule for the current request. Prop K and Prop AA policy assume these funds will not be reimbursed at a rate greater than their proportional share of the funding plan for the relevant phase unless justification is provided for a more aggressive reimbursement rate. If the current request is for multiple phases, please provide separate reimbursement schedules by phase. If the proposed schedule exceeds the years available, please attach a file with the requested information.

Fund Source	FY	2017/18	F	Y 2018/19	F	2019/20	FY	2020/21	FY 2	2021/22+	Total
Prop K	\$	30,000	\$	5,259,722	\$	-	\$	-	\$	-	\$ 5,289,722
Prop AA	\$	-	\$	-	\$	-	\$	-	\$	-	\$ -

## San Francisco County Transportation Authority Project Name: New Traffic Signals Contract 64

## MAJOR LINE ITEM BUDGET

Budget Line Item         Totals         % of contract         SFMTA         Contractor           1. Contract         3. Signals/Mountings         \$ 231,100         \$ 231,100         \$ 231,100           a. Signals/Mountings         \$ 475,700         \$ 475,700         \$ 1,227,285           b. Poles         c. Pullboxes/Conduits         \$ 1,227,285         \$ 1,227,285           d. Wiring         \$ 315,000         \$ 247,500         \$ 324,662           e. Taffic Routing         \$ 247,500         \$ 324,662           f. Miscellaneous         \$ 324,662         \$ 324,662           g. Curb Ramps         \$ 497,350         \$ 497,350           h. Hydraulics         \$ 33,448,897         \$ 33,448,897           s. Controller Cabinets         \$ 130,300         \$ 34,48,897           a. Controller Cabinets         \$ 100,000         \$ 11,250           b. Accessible Ped Signals         \$ 160,000         \$ 11,250           c. Ped Countdown Modules         \$ 11,250         \$ 11,250           d. Wireless Sensors         \$ 30,000         \$ 50,000           e. Cable Car Switches         \$ 50,000         \$ 50,000           e. Cable Car Switches         \$ 508,250         \$ 508,250	CONSTRUCTION						
Totals         % of contract         SFWTA         Contract           \$ 231,100         \$ 231,100         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 1,227,285         \$ 2,227,285	SUMMARY BY MAJOR LINE IT	<b>&gt;</b> =	BY TASK)				
\$ 231,100       \$         \$ 475,700       \$         \$ 1,227,285       \$         \$ 315,000       \$         \$ 324,662       \$         \$ 497,350       \$         \$ 3,448,897       \$         \$ 130,000       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,448,897       \$         \$ \$ 3,449,897       \$         \$ \$ 3,449,897       \$         \$ \$ 3,449,897       \$         \$ \$ 3,449,897       \$         \$ \$ 3,449,897       \$         \$ \$ 3,449,897 <td< th=""><th>Budget Line Item</th><th>Totals</th><th>% of contract</th><th>SFPW</th><th>SFMTA</th><th>ŏ</th><th>ontractor</th></td<>	Budget Line Item	Totals	% of contract	SFPW	SFMTA	ŏ	ontractor
\$ 231,100         \$           \$ 475,700         \$           \$ 1,227,285         \$           \$ 247,500         \$           \$ 324,662         \$           \$ 497,350         \$           \$ 3,448,897         \$           \$ 11,250         \$           \$ 3,448,897         \$           \$ 11,250         \$           \$ 3,448,897         \$           \$ 3,448,897         \$           \$ 3,448,897         \$           \$ 3,448,897         \$           \$ 3,448,897         \$           \$ 3,448,897         \$           \$ 3,448,897         \$           \$ 3,448,897         \$           \$ 3,448,897         \$           \$ 400,000         \$           \$ 400,000         \$           \$ 400,000         \$           \$ 5,000         \$           \$ 5,000         \$           \$ 5,000         \$           \$ 5,000         \$           \$ 5,000         \$           \$ 5,000         \$           \$ 5,000         \$           \$ 5,000         \$           \$ 5,000         \$           \$ 5,	1. Contract						
\$ 475,700         \$ 1,227,285         \$ 1,2	a. Signals/Mountings					↔	231,100
\$ 1,227,285         \$ 1,0           \$ 315,000         \$ 315,000           \$ 247,500         \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	b. Poles					↔	475,700
\$ 315,000         \$           \$ 247,500         \$           \$ 324,662         \$           \$ 497,350         \$           \$ 130,300         \$           \$ 225,000         \$           \$ 11,250         \$           \$ 30,000         \$           \$ 508,250         \$           \$ 508,250         \$           \$ 500,000         \$           \$ 500,000         \$           \$ 500,000         \$           \$ 500,000         \$           \$ 500,000         \$           \$ 500,000         \$           \$ 500,000         \$           \$ 500,000         \$	c. Pullboxes/Conduits					\$	1,227,285
\$ 247,500       \$         \$ 324,662       \$         \$ 497,350       \$         \$ 130,300       \$         \$ 3,448,897       \$         \$ 225,000       \$         \$ 11,250       \$         \$ 82,000       \$         \$ 508,250       \$         \$ 508,250       \$         \$ 508,250       \$         \$ 508,250       \$	d. Wiring					\$	315,000
\$ 324,662       \$ 324,662       \$ \$         \$ 497,350       \$ \$         \$ 130,300       \$ \$         \$ 3,448,897       \$ \$         \$ 225,000       \$ \$         \$ 160,000       \$ \$         \$ \$ \$25,000       \$ \$ \$100,000         \$ \$ \$25,000       \$ \$ \$100,000         \$ \$ \$25,000       \$ \$ \$25,000         \$ \$ \$25,000       \$ \$ \$25,000         \$ \$ \$25,000       \$ \$ \$25,000         \$ \$ \$25,000       \$ \$ \$25,000         \$ \$ \$25,000       \$ \$ \$25,000         \$ \$ \$25,000       \$ \$ \$25,000         \$ \$ \$25,000       \$ \$ \$25,000         \$ \$ \$25,000       \$ \$ \$25,000         \$ \$ \$25,000       \$ \$ \$25,000         \$ \$ \$25,000       \$ \$ \$25,000         \$ \$ \$25,000       \$ \$ \$25,000         \$ \$ \$25,000       \$ \$ \$25,000         \$ \$ \$25,000       \$ \$ \$25,000         \$ \$ \$25,000       \$ \$ \$25,000	e. Traffic Routing					\$	247,500
\$ 497,350         \$           \$ 130,300         \$           \$ 3,448,897         \$         \$         3,           \$ 225,000         \$         \$         \$         3,           \$ 160,000         \$         \$         160,000         \$           \$ 8         \$ 11,250         \$         \$         \$           \$ 8         \$ 30,000         \$         \$         \$           \$ 508,250         \$         \$         \$         \$	f. Miscellaneous					\$	324,662
\$ 130,300       \$ 3,448,897       \$ 3,         \$ 3,448,897       \$ 225,000       \$ 225,000         \$ 160,000       \$ 160,000       \$ 160,000         \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	g. Curb Ramps					\$	497,350
\$ 3,448,897       \$ 3,448,897       \$ 225,000       \$ 225,000         \$ 160,000       \$ 160,000       \$ 160,000         \$ \$ 10,000       \$ 11,250       \$ 11,250         \$ \$ \$2,000       \$ \$20,000         \$ \$ \$20,000       \$ \$20,000         \$ \$ \$208,250       \$ \$208,250	h. Hydraulics					\$	130,300
\$ 225,000 \$ \$ 2 \$ 160,000 \$ \$ 1 \$ 82,000 \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	Subtotal - Contract					\$	3,448,897
elts       \$       225,000       \$       \$       2         Signals       \$       160,000       \$       \$       1         Modules       \$       11,250       \$       \$         s       \$       82,000       \$       \$         nes       \$       \$       \$       \$         \$       \$       \$       \$       \$         \$       \$       \$       \$       \$       \$	2. MTA Provided Materials						
Signals       \$ 160,000       \$ 1         Modules       \$ 11,250       \$ \$         s       \$ 82,000       \$ \$         nes       \$ 30,000       \$ \$         \$ 508,250       \$ \$	a. Controller Cabinets						
Modules       \$ 11,250       \$ \$         s       \$ 82,000       \$ \$         nes       \$ 30,000       \$ \$         \$       \$ 508,250       \$ \$	b. Accessible Ped Signals						
s 82,000 \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	c. Ped Countdown Modules						
nes \$ 30,000 \$ \$ = 2	d. Wireless Sensors						
\$ 508,250   \$	e. Cable Car Switches						
	Subtotal - Materials						

CONSTRUCTION SILIMMARY BY AGENCY	TEM (F		BY T∆SK)					
	1		(NOV)		ľ			
Budget Line Item		Totals	% of contract	SFPW	/	SFMTA	Contractor	
3. Construction Management/								
Support								
a. Construction Engineering	\$	409,724		\$ 12	120,224	\$ 289,500		
b. Construction Management & Inspection	↔	509,000		)9 \$	509,000			
c. Public Affairs	ઝ	103,000		\$ 10	103,000			
d. Materials Testing	↔	000'69		\$	000'69			<u> </u>
e. Wage Check	\$	17,000		\$	17,000			
f. Survey Monuments	\$	27,000		\$	27,000			
g. Sidewalk Legislation	\$	17,000		\$	17,000			
h. Signal Shop Support	\$	100,000				\$ 100,000		
i. Sign Shop Support	\$	47,335				\$ 47,335		
j. Paint Shop Support	\$	70,000				\$ 70,000		
k. Meter Shop Support	\$	10,000				\$ 10,000		
Subtotal - Construction	<del>U</del> .	1 379 059	40%	\$	862 224	\$ 516 835		Π
Management/ Support	<del>)</del>	000,00,-			$\dashv$			
4. Contingency	\$	517,334	15%				\$ 517,334	
5. Other Direct Costs *	\$	200				\$ 500		
TOTAL CONSTRUCTION PHASE	\$	5,854,040		98 \$	862,224	\$ 1,025,585	\$ 3,966,231	_
		-			=			1

\* City Attorney Costs

TR/	ANSPORTAT	ION AUTHO	RITY RECOMMENDATION				
			y Transportation Authority Staff.				
Last Updated:	2/20/2018	Res. No:	Res. Date:				
Project Name:	New Traffic Si	gnals Contrac	t 64				
Grant Recipient:	San Francisco	Municipal Tra	ansportation Agency - DPT				
•	Action	Amount	Phase				
	Prop K	\$5,289,722	Construction (CON)				
Funding	Allocation						
Recommended:							
	Total:	\$5,289,722					
Total Pr	op K Funds:	\$ 5,289,722	Total Prop AA Funds:				
Justification fo	ar multi nhace						
recommendations	-						
multi-sponsor recor	nmendations:						
			Eligible expenses must be incurred prior				
Fund Expira	ation Date:	12/31/2020	to this date.				
Deliverables:							
1. Quarterly progress reports shall provide the percent complete for each							
location and the percent complete for the overall project, in addition to all other requirements described in the Standard Grant Agreement							
			ne project quarterly progress reports				
	should include See SGA for o	•	f work in progress and completed work.				
	See SGA IOI (	Jenniuons.					
Specia	l Conditions:						
1.			n is contingent upon a concurrent Prop				
	_		t to advance a total of \$3,571,249 in the				
			gory from outyears of the Prop K program d Strategic Plan amendment for details.				
2.	The recomme	nded allocatio	n is contingent upon a concurrent New				
	Signals and S	igns 5YPP am	nendment to add the subject project and to				
			473 to the subject project from other th non-Prop K sources, to the subject				
			amendment for details.				
2	The Transport	tation Authority	y will only reimburse SFMTA up to the				
3.			er rate for the fiscal year that SFMTA				
	incurs charges	S.					
Notes:							

### TRANSPORTATION AUTHORITY RECOMMENDATION

### This section is to be completed by Transportation Authority Staff.

**Last Updated:** 2/20/2018 Res. Date: Res. No:

Project Name: New Traffic Signals Contract 64

Grant Recipient: San Francisco Municipal Transportation Agency - DPT

Metric	Prop K	Prop AA
Actual Leveraging - Current Request	9.64%	No Prop AA
Actual Leveraging - This Project	17.36%	No Prop AA

**SFCTA Project** 

Reviewer: P&PD

### SGA PROJECT NUMBER

Sponsor: San Francisco Municipal Transportation Agency - DPT

Name: New Traffic Signals Contract 64 131-907xxx **SGA Project Number:** 

Phase: Construction (CON) Fund Share:

i ilasc.	Construction (C	JOIN)			rund Share:	90.36%
	Cash Flow	<b>Distribution</b>	Schedule by	Fiscal Year		
Fund Source	FY 2017/18	FY 2018/19	FY 2019/20	FY 2020/21	FY 2021/22+	Total
Prop K	\$30,000	\$5,259,722				\$5,289,722

Project Name: New Traffic Signals Contract 64

Grant Recipient: San Francisco Municipal Transportation Agency - DPT


1) The requested sales tax and/or vehicle registration fee revenues will be used to supplement and under no circumstance replace existing local revenues used for transportation purposes.

### Required for Allocation Request Form Submission

Initials of sponsor staff member verifying the above statement

### $\mathsf{TM}$

	CONTACT IN	FORMATION
	Project Manager	Grants Section Contact
Name:	Geraldine de Leon	Tim Manglicmot
Title:	Engineer	Acting Manager of Grants Procurement & Management
Phone:	415-701-4675	415-646-2517
Email:	Geraldine.DeLeon@sfmta.com	Timothy.Manglicmot@sfmta.com



Α	Bryant Street & Sterling Street
В	7th Street & Minna Street
С	Mariposa Street & Pennsylvania Avenue
D	Ellis Street & Webster Street
Е	Mission Street & Highland Avenue
F	Owens Street & Campus Way
G	15th Street & Dolores Street
Н	Alemany Boulevard & Foote Avenue
I	Leavenworth Street & Washington Street

### FACTORS AFFECTING CURRENT BID PRICES (January 18, 2018)

### **GENERAL FACTORS**

The economy is booming and there is an unprecedented amount of construction activity, especially in San Francisco and the Bay Area. The types of construction projects impacted include government initiated projects, private utility projects and many privately funded projects. Many potential bidders/contractors are extremely busy and do not need or want additional work. Some contractors may be reaching their bonding limits (which ensures the construction will be completed if the contractor cannot complete the work) and cannot bid until the bonds are released.

### **RECENT BID RESULTS:**

Signal Projects	Eng. Estimate	Low Bid	<u>Date</u>	% of Estimate
New Signal Contract 63	\$1,427,000	\$1,398,000	11/30/16	97.9
Walk First New Traffic Signals	\$2,511,582	\$2,453,858	03/15/17	97.7
Auto Photo Enforcement	\$1,887,123	\$2,002,270	10/4/17	106.1
Signal Modification Contract 34	\$3,399,410	\$3,990,810	11/08/17	117.4
Multi-Discipline Projects				
Polk Street Streetscape	\$13,180,740	\$18,321,751	Feb. 2016	139
#22 Fillmore TSP (rough est.)	\$51,000,000	\$72,000,000	Dec. 2017	141

### ACTIONS TO CONSIDER AFTER BID OPENING

Award the project (and secure additional funds as necessary).

Rebid the project.

Change/reduce scope and rebid the project.

Withdraw or "hold" the project for a later date.

Factors Affecting Current Bid Prices (1-18-18), Page 2

### SPECIFIC FACTORS FOR TRAFFIC SIGNAL PROJECTS

Traffic signal work is generally divided into two categories: electrical and civil.

For locally funded projects, the City requires the electrical contractors to utilize LBE (Local Business Enterprise) contractors/suppliers for a specified goal amount (as determined by DPW) of the contract work (typically 25%) or show a good faith effort of why the goals could not be met. In addition, San Francisco also allows a 10% bid preferences for LBE contractors. This means that the LBE bids are discounted 10% during bid comparison, but the LBE contractors are paid the full bid amount.

For projects where the funds are obtained through Caltrans, a DBE (Disadvantaged Business Enterprise i. e. woman owned, minority owned) goal is established and the program is administered by Caltrans.

The above requirements may discourage certain contractors from bidding in San Francisco. In the past few years there have been only two companies that consistently bid on traffic signal projects (Bay Area Light Works and Phoenix Electric). However, for the last few bids, the only consistent bidder is Bay Area Light Works.

### NEW SIGNAL CT. 64

This scope of this project is to construct new traffic signals at 9 intersections. The original project budget was \$3,600,000 (or about \$400,000 per signal). The updated project cost estimate is \$6,554,040 (or about \$730,000 per signal).

A review of recent low bids show unit prices for the following:

	Ct. 63	Ct. 34	
<u>Conduits</u>	11/30/16	11/8/17	% Increase
1 -2 inch PVC (linear foot)	\$70	\$100	42%
1-2 inch GRS (linear foot)	\$85	\$120	41%
4- 2 inch HDPE (linear foot)	\$100	N/A	
Curb Ramps (each)	\$10,000	\$17,000	70%

The typical costs of city furnished items are shown below:

New controller and cabinet \$20,000 \$25,000 25%

The latest bid prices have been used to prepare the cost estimates for this project.

### Prop K 5-Year Project List (FY 2014/15 - 2018/19) Programming and Allocations to Date Pending March 20, 2017 Board New Signals and Signs (EP 31)

	-		rending in	Fending March 20, 2017 Board	ırd				
					-	Fiscal Year			
Agency	Project Name	Phase(s)	Status	2014/15	2015/16	2016/17	2017/18	2018/19	Total
New Equipment	ment								
SFMTA	New Equipment <sup>7</sup>	PROC	Programmed		0\$				0\$
Follow-the-Paving	-Paving								
SFMTA	Follow-the-Paving (New Pavement Markers and Conduits) <sup>3</sup>	CON/ PROC	Programmed	0\$					0\$
SFMTA	Traffic Signal Conduit Contract	CON	Allocated		\$150,000				\$150,000
SFMTA	Follow-the-Paving (New Pavement Markers and Conduits) <sup>7</sup>	CON/ PROC	Programmed			0\$			0\$
SFMTA	Follow-the-Paving (New Pavement Markers and Conduits) <sup>7</sup>	CON/ PROC	Programmed					\$150,000	\$150,000
New Traffic Signals	c Signals								
SFMTA	New Traffic Signals (Contract 62) 4	CON	Programmed		0\$				\$0
SFMTA	New Traffic Signals (Contract 62)	CON	Allocated		\$1,500,000				\$1,500,000
SFMTA	New Signal Contract 62 <sup>1</sup>	CON	Allocated	\$150,000					\$150,000
SFMTA	New Traffic Signals (5 Locations) <sup>2, 4</sup>	PS&E	Programmed	0\$					\$0
SFMTA	New Signal Contract 63 <sup>2</sup>	PS&E	Allocated	\$280,000					\$280,000
SFMTA	New Traffic Signals (5 Locations) 4	CON	Programmed			0\$			0\$
SFMTA	New Signals Contract 63 <sup>4</sup>	CON	Allocated			\$1,700,000			\$1,700,000
SFMTA	New Traffic Signals (Contract 63) - Additional Funds <sup>6</sup>	CON	Allocated			\$360,000			\$360,000
SFMTA	New Traffic Signals (5 Locations) <sup>5, 6</sup>	PS&E	Programmed			0\$			0\$
SFMTA	New Traffic Signals (Contract 64) <sup>5</sup>	PS&E	Allocated			\$126,514			\$126,514
SFMTA		CON	Pending				\$5,289,722		\$5,289,722
Safe Streets									
SFMTA	Active Transportation Program Local Match	PS&E, CON	Programmed			\$975,000			\$975,000
SFMTA	Active Transportation Program Local Match	PS&E, CON	Programmed					\$231,250	\$231,250
SFMTA	New Pavement Markers <sup>7</sup>	CON	Programmed			0\$			80
SFMTA	New Pavement Markers <sup>7</sup>	CON	Programmed					\$200,000	\$200,000
SFMTA	New Pedestrian Countdown Signals <sup>7</sup>	PS&E, CON	Programmed			0 <b></b>			0\$
SFMTA	New Traffic Signs <sup>7</sup>	CON	Programmed			0\$			0\$
SFMTA	New Traffic Signs <sup>7</sup>	CON	Programmed					\$300,000	\$300,000
SFMTA	Neighborhood Transportation Improvement Program	PS&E, CON	Programmed		\$500,000				\$500,000

## Prop K 5-Year Project List (FY 2014/15 - 2018/19) New Signals and Signs (EP 31)

**Programming and Allocations to Date**Pending March 20, 2017 Board

						Fiscal Year			
Agency	Project Name	Phase(s)	Status	2014/15	2015/16	2016/17	2017/18	2018/19	Total
		Total Prog	rogrammed in 5YPP	\$430,000	\$2,150,000	\$3,161,514	\$5,289,722	\$881,250	\$11,912,486
	Total Allocated and	cated and l	d Pending in 5YPPs	\$430,000	\$1,650,000	\$2,186,514	\$5,289,722	0\$	\$9,556,236
		Total Deol	Total Deobligated in 5YPPs	0\$	0\$	0\$	0\$	0\$	0\$
		Total Una	Total Unallocated in 5YPPs	0\$	\$500,000	\$975,000	0\$	\$881,250	\$2,356,250
	Total Programmed in	ammed in 2	n 2014 Strategic Plan	\$525,000	\$2,035,000	\$2,850,000	\$5,289,722	\$881,250	\$11,580,972
	Deobligate	ed from Pric	Deobligated from Prior 5YPP Cycles **	\$338,828					\$338,828
	Cumulative Remaining Programming Capacity	ining Progra	amming Capacity	\$433,828	\$318,828	\$7,314	\$7,314	\$7,314	\$7,314

Pending Allocation/Appropriation Programmed

Board Approved Allocation/Appropriation

# Prop K 5-Year Project List (FY 2014/15 - 2018/19)

### New Signals and Signs (EP 31) Programming and Allocations to Date

Pending March 20, 2017 Board

	Total		
	2018/19		
	2017/18		
Fiscal Year	2016/17		
	2015/16		
	2014/15		
	Status		
	Phase(s)		
	Project Name		
	ncy		

### FOOTNOTES:

Agen

- <sup>1</sup> Added FY 2014/15 construction funds for New Traffic Signals (Contract 62) with \$150,000 in funds deobligated from the design phase.
- <sup>2</sup> To accommodate allocation of \$280,000 for New Traffic Signals (Contract 63) (Resolution 2015-056, 5/19/14):
- Reduced placeholder for New Traffic Signals (5 Locations) from \$375,000 in FY 2014/15 design funds to \$90,000.
- Added New Traffic Signals (Contract 63) with \$280,000 in FY 2014/15 design funds.
- <sup>3</sup> To accommodate allocation of \$150,000 for Traffic Signal Conduit Contract (Resolution 2015-061, 6/23/15):
- Reduced placeholder for Follow-the-Paving (New Pavement Markers and Conduits) from \$150,000 in FY 2014/15 construction/ procurement funds to \$0. Added Traffic Signal Conduit Contract with \$150,000 in FY 2015/16 consturction funds.
- <sup>4</sup> 5YPP Amendment to fully fund the construction phase of New Traffic Signals (Contract 63) (Resolution 2017-002, 07/26/16):
- New Traffic Signals (Contract 62): Reduced remaining construction funds from \$35,000 in FY 2015/16 funds to \$0. Project completed under budget.
- New Traffic Signals (5 Locations): Reduced remaining design funds from \$95,000 in FY 2014/15 to \$0. Design phase of New Traffic Signals (Contract 63), completed under
- Deobligations from prior 5YPP cycles: Reduced by \$70,000 from \$188,828 to \$118,828.
- New Traffic Signals (5 Locations): Reduced placeholder from \$1,500,000 in FY 2016/17 construction funds to \$0.
- New Traffic Signals (Contract 63): Added project with \$1,700,000 in FY 2016/17 construction funds.
- <sup>5</sup> To accommodate allocation of \$126,514 for New Traffic Signals (Contract 64) (Resolution 2017-035, 03/21/17):
- Reduced placeholder for New Traffic Signals (5 Locations) from \$375,000 in FY 2016/17 design funds to \$248,486.
  - Added the design phase of New Traffic Signals (Contract 64) with \$126,514 in FY 2016/17 design funds.
- <sup>6</sup> 5YPP Amendment to fully fund New Traffic Signals (Contract 63) Additional Funds (Resolution 2017-035, 03/21/17):
- New Traffic Signals (5 Locations): Reduced remaining design funds from \$248,486 in FY 2016/17 to \$0. The design phase of New Traffic Signals (Contract 64) is fully funded in FY 2016/17 (see footnote 5).
- Deobligations from prior 5YPP cycles: Reduced by \$111,514 from \$118,828 to \$7,314.
- New Traffic Signals (Contract 63) Additional Funds: Added project with \$360,000 in FY 2016/17 construction funds.
- <sup>7</sup> 5YPP amendment to fully fund New Traffic Signals Contract 64 (Resolution 2018-XXX, xx/xx/2018):
- New Equipment: Reduced remaining funds from \$200,000 in FY 2015/16 to \$0.
- Follow-the-Paving (New Pavement Markers and Conduits): Reduced from \$150,000 in FY 2016/17 to \$0.
- New Pavement Markers: Reduced from \$200,000 in FYs 2016/17 to \$0.
- New Pedestrian Countdown Signals: Reduced from \$868,473 in FY 2016/17 to \$0.
- New Traffic Signs: Reduced from \$300,000 in FY 2016/17 to \$0.
- To accommodate the allocation of the remaining \$2,913,935, action included a Strategic Plan amendment to advance \$1,320,000 in undesignated FY2019/20 funds,
  - \$1,359,600 in undesignated FY2020/21 funds, and \$305,000 in undesignated FY2021/22 funds; and to program \$586,649 in unprogrammed capacity.

New Signals and Signs (EP 31)
Cash Flow (\$) Maximum Annual Reimbursement
Pending March 20, 2017 Board Prop K 5-Year Project List (FY 2014/15 - 2018/19)

			0		4.4			
				Fiscal Year	Year			
Project Name	Phase	2014/15	2015/16	2016/17	2017/18	2018/19	2019/20	Total
New Equipment								
New Equipment7	PROC		0\$	0\$				0\$
Follow-the-Paving								
Follow-the-Paving (New Pavement Markers and Conduits) 3	CON/ PROC	O <b>\$</b>						0\$
Traffic Signal Conduit Contract	CON		\$150,000					\$150,000
Follow-the-Paving (New Pavement Markers and Conduits)7	CON/ PROC			0\$				0\$
Follow-the-Paving (New Pavement Markers and Conduits)7	CON/ PROC					\$150,000		\$150,000
New Traffic Signals								
New Traffic Signals (Contract 62) 4	CON		0\$	0\$				0\$
New Traffic Signals (Contract 62)	CON		\$767,500	\$732,500				\$1,500,000
New Signal Contract 62 1	CON	\$50,000	\$100,000					\$150,000
New Traffic Signals (5 Locations) 2, 4	PS&E	\$0	0\$					\$
New Signal Contract 63 2	PS&E		\$280,000					\$280,000
New Traffic Signals (5 Locations) 4	CON			0\$	\$0			80
New Signals Contract 63 4	CON			\$950,000	\$750,000			\$1,700,000
New Traffic Signals (Contract 63) - Additional Funds 6	CON				\$360,000			\$360,000
New Traffic Signals (5 Locations) 5, 6	PS&E			80	\$0			\$0
New Traffic Signals (Contract 64) 5	PS&E			\$30,000	\$96,514			\$126,514
New Traffic Signals (Contract 64) 7	CON				\$30,000	\$5,259,722		\$5,289,722
Safe Streets								
Active Transportation Program Local Match	PS&E, CON			\$487,500	\$487,500			\$975,000
Active Transportation Program Local Match	PS&E, CON					\$231,250		\$231,250
New Pavement Markers7	CON			0\$	0\$			0\$
New Pavement Markers7	CON					\$100,000	\$100,000	\$200,000
New Pedestrian Countdown Signals7	PS&E, CON			0\$	0\$	<b>0</b>		0\$
New Traffic Signs7	CON			0\$	0\$			0\$
New Traffic Signs7	CON					\$150,000	\$150,000	\$300,000
Neighborhood Transportation Improvement Program	PS&E, CON		\$250,000	\$250,000				\$500,000

# Prop K 5-Year Project List (FY 2014/15 - 2018/19)

New Signals and Signs (EP 31)
Cash Flow (\$) Maximum Annual Reimbursement
Pending March 20, 2017 Board

			remark march 20, 2017 Dome	TOT DOWN				
				Fiscal Year	Year			
Project Name	Phase	2014/15	2015/16	2016/17	2017/18	2018/19	2019/20	Total
Total (	Total Cash Flow in 5YPP	\$50,000	\$1,547,500	\$2,450,000	\$1,724,014	\$5,890,972	\$250,000	\$11,912,486
Total Cas	Total Cash Flow Allocated	\$50,000	\$1,297,500	\$1,712,500	\$1,236,514	\$5,259,722	0\$	\$9,556,236
Total Cash I	Total Cash Flow Deobligated	0\$	0\$	0\$	0\$	0\$	0\$	0\$
Total Cash 1	Total Cash Flow Unallocated	0\$	\$250,000	\$737,500	\$487,500	\$631,250	\$250,000	\$2,356,250
Total Cash Flow in 2014 Strategic Plan	2014 Strategic Plan	\$337,500	\$1,205,000	\$2,442,500	\$1,455,000	\$5,890,972	\$250,000	\$11,580,972
Deobligated from Prior 5YPP Cycles **	or 5YPP Cycles **	\$338,828						\$338,828
Cumulative Remaining Cash Flow Capacity	Cash Flow Capacity	\$626,328	\$283,828	\$276,328	\$7,314	\$7,314	\$7,314	\$7,314
Programmed								
Pending Allocation/Appropriation								
Board Approved Allocation/Appropriation								

## Adopted and Proposed Amended Strategic Plan Pending March 2018 Board Action

EP No.	EP Line Item	Total Available Funds	Percent of Available Funds Spent on Financing	Total 30-year Programming & Finance Costs	93	FY2017/18	FY2018/19	FY2019/20	FY2020/21	FY2021/22
Adopted 2014 P Amendment 10	Adopted 2014 Prop K Strategic Plan - Amendment 10									
				Programming \$ 43,744,970	\$ 026		\$ 881,250	\$ 1,320,000	\$ 1,359,600	1,400,388
31	New Signals and Signs	\$ 45,372,115	1.20%	Finance Costs \$ 544,106	\$ 901	66,129	\$ 42,001	\$ 28,576	\$ 61,916 \$	56,052
				Total \$ 44,289,076	\$ 920	66,129	\$ 923,251	\$ 1,348,576	\$ 1,421,516 \$	1,456,440
Proposed 20 (Programmi capacity)	Proposed 2014 Prop K Strategic Plan - Amendment 11 (Programming advanced from FYs 19/20 - 21/22 + \$586,649 in unprogrammed capacity)	nent 11 22 + \$586,649 in u	nprogrammed	_						
				Programming \$ 44,331,619	\$ 619	5,289,722	\$ 881,250			1,095,388
31	New Signals and Signs	\$ 45,372,107	2.29%	Finance Costs \$ 1,037,465	\$ \$	27,655	\$ 115,486	\$ 84,292	\$ 132,389 \$	91,826
				Total \$ 45,369,084	\$	5,317,377	\$ 996,736	\$ 84,292	\$ 132,389 \$	1,187,214
Change										
				Programming \$ 586,649	\$	5,289,722	- \$	\$ (1,320,000) \$	\$ (1,359,600) \$	(305,000)
31	New Signals and Signs	(8)	1.09%	Finance Costs \$ 493,359	\$ 658	(38,474) \$	\$ 73,485	\$ 55,716	\$ 70,474 \$	35,774
				Total \$ 1,080,008	\$ 800	5,251,248	\$ 73,485	\$ (1,264,284) \$	\$ (1,289,126) \$	(269,226)

Prop K Total	-					
Adopted 2014 P Amendment 10	Adopted 2014 Prop K Strategic Plan - Amendment 10					
				Programming	\$ 2,526,	2,526,251,506
Prop K	Total Prop K Strategic Plan	\$ 2,922,166,452	8.75%	Finance Costs	\$ 255,	255,647,465
				Total	\$ 2,781,8	2,781,898,971
Proposed 2C (Programmi capacity)	Proposed 2014 Prop K Strategic Plan - Amendment 11 (Programming advanced from FYs 19/20 - 21/22 + \$586,649 in unprogrammed capacity)	nent 11 22 + \$586,649 in u	unprogrammed			
				Programming \$		2,526,838,155
Prop K	Total Prop K Strategic Plan	\$ 2,922,165,986	8.76%	Finance Costs \$		255,865,392
				Total	\$ 2,782,	2,782,703,547
Change						
				Programming	\$	586,649
Prop K	Total Prop K Strategic Plan	\$ (466)	0.01%	Finance Costs	\$	217,927
				Total	\$	804,576

## Adopted and Proposed Amended Strategic Plan Pending March 2018 Board Action

FY2033/34	1,996,618	٠	1,996,618	1,996,618		1,996,618	٠		
	↔	↔	€9	€	↔	↔	₩	\$	\$
FY2032/33	1,938,465	-	1,938,465	1,938,465	•	1,938,465			
	₩.	↔	₩.	₩.	₩.	↔	₩	\$	\$
FY2031/32	1,882,004	1	1,882,004	1,882,004		1,882,004			
	₩.	↔	₩.	₩.	₩.	↔	₩	\$	\$
FY2030/31	1,827,189		1,827,189	1,827,189	25,099	1,852,288		25,099	25,099
	↔	\$	\$	↔	↔	↔	<del>\\$</del>	\$	<b>⇔</b>
FY2029/30	1,773,970	2,675	1,776,645	1,773,970	47,925	1,821,895	٠	45,250	45,250
	↔	\$	\$	↔	↔	↔	<del>69</del>	\$	↔
FY2028/29	1,722,301	22,362	1,744,663	1,722,301	99,760	1,783,061	٠	38,398	38,398
_	€9	↔	₩.	₩.	€9	↔	₩	\$	↔
FY2027/28	1,672,137	30,624	1,702,761 \$	1,672,137	66,358	1,738,495		35,734	35,734
_	₩.	↔	↔	<del>\$</del>	₩.	↔	↔	\$	\$
FY2026/27	1,623,434	33,980	1,657,414	1,623,434	68,683	1,692,117		34,703	34,703
_	↔	↔	₩.	₩.	↔	↔	↔	\$	€9
FY2025/26	1,576,149	37,220	1,613,369	1,576,149	67,845	1,643,994	٠	30,626	30,626
	<del>\$</del>	\$	€9	<del>\$</del>	<del>\$</del>	↔	<del>⇔</del>	↔	↔
FY2024/25	1,530,242	41,740	1,571,982	1,530,242	711,977	1,602,219	٠	30,237	30,237
	₩.	₩.	₩.	↔	↔	\$	€9	₩	\$
FY2023/24	1,485,672	48,262	1,533,934 \$	1,485,672	79,763	1,565,435	٠	31,501	31,501
	↔	\$	₩.	↔	↔	\$	₩	€\$	€9
FY2022/23	1,442,400	53,949	1,496,349 \$	1,442,400 \$	85,175	1,527,574	٠	31,225	31,225
	<del>\$</del>	↔	<del>\$</del>	↔	<del>\$</del>	↔	€9	€9	€9



**This Page Intentionally Left Blank** 

FY of Allocation Action: 2	2017/18
Project Name: <u>I</u>	ntelligent Transportation Systems - Variable Message Signs
Grant Recipient:	San Francisco Municipal Transportation Agency - DPT
EXPENDITURE PLAN INFORMA	TION
Prop K EP category: <u>/</u>	Advanced Technology and Information Systems (SFgo): (EP-32)
Prop K EP Line Number (Primary): _ Prop K Other EP Line Numbers: _	
Prop AA Category: _	
	Current Prop AA Request:
Supervisorial District(s):	District 03, District 05, District 10
Supervisorial District(s).	District 03, District 03, District 10
REQUEST	
Brief Project Description (type below	w)
These signs are used to show real-time	igns and related hardware at 22 existing locations in Districts 3, 5, 6 and 10. ne information about current and future traffic conditions, parking garage ts. The equipment to be replaced and upgraded, such as displays and useful life.
Detailed Scope, Project Benefits an	d Community Outreach (type below)
See next page for detailed project des	cription.
Project Location (type below)	
Embarcadero and Mission, Fremont a King and 3rd, 3rd and Harrison, 4th ar	nd Howard, King and 2nd, Howard and New Montgomery, Kearny and Pine, and Minna, King and 5th, 5th and Harrison, Folsom and 6th, 6th and Howard, h and Mission, 9th and Howard, 10th and Mission, Franklin and Fell, Gough Marin, Paul and 3rd
Project Phase (select dropdown bel	low)
Construction (CON)	
Map or Drawings Attached?	Yes
Other Items Attached?	No
5YPP/STRATEGIC PLAN INFOR	MATION
Type of Project in the Prop K 5YPP/Prop AA Strategic Plan?	New Project
Please describe and justify the nece	
	to the Advanced Technology and Information Systems (SFgo) 5YPP to re- controller Upgrades placeholder to the subject project. SFgo Controller op K sources.

### Detailed Scope, Project Benefits and Community Outreach (type below)

<u>Scope:</u> SFMTA will use funds to purchase and replace existing Intelligent Transportation Systems (ITS) equipment such as: Variable Message Sign (VMS) displays and controllers, network communication devices (e.g. network switches, routers,) and other related hardware and equipment (purchases include extended warranty). VMS displays are used to show messages about current and future traffic conditions, parking garage space availability and emergency alerts.

The existing hardware was installed across multiple phases in 2003, 2008 and 2011. Hardware has reached end of life and will require replacement. Problems include: (1) broken display modules that result in blacked out portions of the VMS display and (2) communication issues to the VMS controller which would result in the inability to remotely send messages to the display. Specifically VMS controllers (used to relay messages from the traffic management center to the sign) are no longer supported by the manufacturer. Signs with faulty VMS controllers and displays require the engineer to program messages at the sign itself or foregoing the display of the messages altogether. The sign locations are concentrated in supervisorial districts 3, 5, 6 and 10.

Benefits: The benefits from the proposed investment will include the following:

(1) The display of parking garage space availability allows people to decide in advance where to park their car. This reduces the need to wander around city streets to look for parking. Hence reducing traffic congestion and pollution.
(2) VMS is utilized to display messages on major planned and unplanned street closures. This function alerts vehicles to either detour away or avoid the closure area allowing street space for transit to operation and to allow the poice, fire fighters and emergecy medical personnel to respond in a safe and optimal manner.

<u>Implementation:</u> SFMTA Sustainable Streets will manage the issuance and administration of purchase orders for VMS related equipment. Other city agencies will be needed for support (1) Department of Technology to upgrade the existing IT network and ensure compatibility with new ITS devices and (2) Public Works for the installation and removal of existing VMS infrastructure.

SFMTA staff will play 3 essential roles to ensure proper project implementation:

- > Engineering: sets up purchase order with vendor; coordinates construction and maintenance activities between vendor, Signal Shop, Information Technology (IT) and Department of Technology; evaluates the decision to repair or replace defective VMS items based on vendor, IT and signal shop feedback; provides traffic control plans; programs operation of signs.
- <u>> Signal Shop:</u> provide construction and maintenance support to vendor, Engineering, IT and Department of Technology; performs tests and checks on network connected equipment; reconfigures network connected devices based on requests from IT, maintains electrical connections and equipment.
- <u>> Information Technology:</u> provides construction and maintenance support to engineering, vendor and signal shop; monitors, configures and troubleshoot network issues.

<u>Community Outreach:</u> Community outreach was performed for the original installation of the VMS during their respective phases in 2003 and 2011. The upgrades of existing VMS will not require additional outreach.

Project Name: Intelligent Transportation Systems - Variable Message Signs

### **ENVIRONMENTAL CLEARANCE**

**Environmental Type**: Categorically Exempt

### PROJECT DELIVERY MILESTONES

Enter dates below for ALL project phases, not just for the current request, based on the best information available. For PLANNING requests, please only enter the schedule information for the PLANNING phase.

Phase	S	tart	E	nd
Filase	Quarter	Calendar Year	Quarter	Calendar Year
Planning/Conceptual Engineering (PLAN)				
Environmental Studies (PA&ED)			Jul-Sep	2008
Right-of-Way				
Design Engineering (PS&E)				
Advertise Construction				
Start Construction (e.g. Award Contract)	Apr-Jun	2018		
Operations (i.e., paratransit)				
Open for Use	Apr-Jun	2018	Oct-Dec	2018
Project Completion (means last eligible expenditure)			Apr-Jun	2019

### SCHEDULE DETAILS

Provide dates for any COMMUNITY OUTREACH planned during the requested phase(s). Identify PROJECT COORDINATION with other projects in the area (e.g. paving, MUNI Forward) and relevant milestone dates (e.g. design needs to be done by DATE to meet paving schedule). List any timely use-of-funds deadlines (e.g. federal obligation deadline). If a project is comprised of MULTIPLE SUB-PROJECTS, provide milestones for each sub-project. For PLANNING EFFORTS, provide start/end dates for each task.

Warranty will be pre-purchased, and no expenses will be incurred after installations are complete.

August 2008: Obtained CEQA Categorical Exemption Determination from the City and County of San Francisco

Existing conduit is in place for fiber but currently fiber is not in place at all locations. There will be coordination with the Department of Technology to pull fiber within our existing conduit to establish a connection to the SFMTA network.

Project Name: Intelligent Transportation Systems - Variable Message Signs

### **FUNDING PLAN - FOR CURRENT REQUEST**

Enter the funding plan for the phase(s) that are the subject of the CURRENT REQUEST. Totals should match those shown in the Cost Summary below.

Fund Source	Planned	Programmed	Allocated	Total
Prop K	\$ 1,000,000	\$ -	\$ -	\$ 1,000,000
Prop AA	\$ -	\$ -	\$ -	\$ -
Total:	\$ 1,000,000	\$ -	\$ -	\$ 1,000,000

### **COST SUMMARY**

Show total cost for ALL project phases (in year of expenditure dollars) based on best available information. Source of cost estimate (e.g. 35% design, vendor quote) is intended to help gauge the quality of the cost estimate, which should improve in reliability the farther along a project is in its development.

Phase	Total Cost	Prop K - Current Request	Prop AA - Current Request	Source of Cost Estimate
Planning/Conceptual Engineering (PLAN)	\$ -	\$ -		
Environmental Studies (PA&ED)	\$ -	\$ -		
Right-of-Way	\$ -	\$ -		
Design Engineering (PS&E)		\$ -	\$ -	
Construction (CON)	\$ 1,000,000	\$ 1,000,000	\$ -	Vendor Quote + engineer's estimate
Operations (Paratransit)	\$ -	\$ -		
Total:	\$ 1,000,000	\$ 1,000,000	\$ -	

% Complete of Design:	NA	as of	NA
<b>Expected Useful Life:</b>	15 Years	_	

### PROPOSED REIMBURSEMENT SCHEDULE FOR CURRENT REQUEST (instructions as noted below)

Use the table below to enter the proposed reimbursement schedule for the current request. Prop K and Prop AA policy assume these funds will not be reimbursed at a rate greater than their proportional share of the funding plan for the relevant phase unless justification is provided for a more aggressive reimbursement rate. If the current request is for multiple phases, please provide separate reimbursement schedules by phase. If the proposed schedule exceeds the years available, please attach a file with the requested information.

Fund Source	FY	2016/17	FY	2017/18	FY	2018/19	FY	2019/20	FY	2020/21+	Total
Prop K	\$	-	\$	100,000	\$	900,000	\$	-	\$	-	\$ 1,000,000
Prop AA	\$	-	\$	-	\$		\$	-	\$	-	\$ -

Project Name: Intelligent Transportation Systems - Variable Message Signs

## MAJOR LINE ITEM BUDGET

## CONSTRUCTION

SUMMARY BY MAJOR LINE ITEM (BY AGENCY LABOR	OR BY TASK)				
Budget Line Item	Totals	% of contract	SFPW/DT	SFMTA	Contractor
Purchase Order	\$ 400,000	40%			\$ 400,000
VMS Equipment	\$ 250,000	72%			\$ 250,000
VMS Controller (22 controllers x \$4500 each)	\$ 100,000	10%			\$ 100,000
Power Supply Equipment	\$ 25,000	%E			\$ 25,000
Sign Pixel Module Replacement	\$ 20,000	%9			\$ 50,000
Miscellaneous Parts	\$ 20,000	%5			\$ 50,000
Vendor Repair Diagnostics	\$ 25,000	3%			\$ 25,000
VMS Extended Warranty	\$ 150,000	15%			\$ 150,000
<b>SSD Signal Shop Support</b> (cost per location varies)	150,000	15%		150,000	
SSD Engineering	\$ 150,000	15%		150,000	
Work Authorizations to other City Agencies	300,000	<b>%0</b> E	300,000		
Department of Technology	\$ 250,000	72%	\$ 250,000		
Public Works	\$ 50,000	2%	\$ 50,000		

4	000,000,1
eering and	
e Grand Total (Purchase Orders+Engineering and	Signal Shop Support+Work Authorizations)
Phase Grand To	Signal Shop Sup

			JRITY RECOMMENDATION	
<u>This s</u>	ection is to be	e completed	by Transportation Authority Staff.	
Last Updated:	2/21/2018	Res. No:	Res. Date:	ı
Project Name:	Intelligent Tra	nsportation S	ystems - Variable Message Signs	
Grant Recipient:	San Francisco	o Municipal Tr	ransportation Agency - DPT	
	Action	Amount	Phase	!
	Prop K	\$1,000,000	Construction (CON)	
Funding Recommended:	Allocation			
i unumg Kecommended.				
	Total:	\$ 1,000,000		
Total P	rop K Funds:	\$ 1,000,000	Total Prop AA Funds:	\$
			Eligible evenence must be incurred write.	
Fund Expir	ration Date:	12/31/2019	Eligible expenses must be incurred prior to this date.	
Dallana	-1.1		•	
Delivera 1.				1
	Quarterly prog	-	shall report the number and locations of	
		, 0	ded or replaced and the percent pject, in addition to all other requirements	
	·	•	Grant Agreement (SGA). Over the life of	
			ss reports should include 2-3 photos of	
			photo showing the Prop K logo affixed	
	to the new eq	uipment. See	SGA for definitions.	
				I
Special	Conditions:			l
1.	The recomme	ended allocation	on is contingent upon an amendment to	
			and Information Systems (SFgo) 5YPP to	
			m the SFgo Controller Upgrades	
	for details.	o trie subject p	project. See attached 5YPP amendment	
2	The Transper	tation Authori	travill only reimburge SEMTA up to the	
2.	•		ty will only reimburse SFMTA up to the ier rate for the fiscal year that SFMTA	
	incurs charge			
Nat				:
Notes:				1
		•	re required on equipment purchased with d Grant Agreement for details.	
	IF TOP IN TUITIUS.	Jee Standan	u Grant Agreement for details.	1

### TRANSPORTATION AUTHORITY RECOMMENDATION

### This section is to be completed by Transportation Authority Staff.

Last Updated: 2/21/2018 Res. No: Res. Date:

Project Name: Intelligent Transportation Systems - Variable Message Signs

Grant Recipient: San Francisco Municipal Transportation Agency - DPT

Metric	Prop K	Prop AA
Actual Leveraging - Current Request	0.00%	No Prop AA
Actual Leveraging - This Project	0.00%	No Prop AA

**SFCTA Project** 

Reviewer: P&PD

### SGA PROJECT NUMBER

Sponsor: San Francisco Municipal Transportation Agency - DPT

SGA Project Number: 132-XXXXXX Name: Intelligent Transportation Systems - Variable Message

Signs

 Phase: Construction (CON)
 Fund Share: 100.00%

 Cash Flow Distribution Schedule by Fiscal Year

 Fund Source
 FY 2016/17
 FY 2017/18
 FY 2018/19
 FY 2019/20
 FY 2020/21+
 Total

 Prop K
 \$ 100,000
 \$ 900,000
 \$1,000,000

Project Name: Intelligent Transportation Systems - Variable Message Signs

Grant Recipient: San Francisco Municipal Transportation Agency - DPT

1) The requested sales tax and/or vehicle registration fee revenues will be used to supplement and under no circumstance replace existing local revenues used for transportation purposes.


Required for Allocation Request Form Submission
Initials of sponsor staff member verifying the above statement

TM


	CONTACT INFORI	MATION
	Project Manager	Grants Section Contact
Name:	Robert Lim	Elias Girma
Title:	Associate Engineer	Principal Analyst
Phone:	415-701-5669	415-646-2518
Email:	Robert.Lim2@sfmta.com	elias.girma@sfmta.com

### MAPS AND DRAWINGS

This map and table shows the 22 existing VMS. Signs # 23 and 24 will be installed as part of the Van Ness BRT project. Parking garages for which parking information is provided via VMS are shown as letters A through M.



### MAPS AND DRAWINGS



**VMS** Display



**VMS Controller** 

# Prop K 5-Year Project List (FY 2014/15 - 2018/19) Advanced Technology and Information Systems (SFgo) (EP 32) Programming and Allocations to Date

Board	
2018	
20,	
March	
nding	
6	

						Fiscal Year			
	Project Name	Phase(s)	Status	2014/15	2015/16	2016/17	2017/18	2018/19	Total
	SFMTA SFgo Controller Upgrades <sup>1,2</sup>	PROC	Programmed		0\$				0\$
SFMTA	SFgo Controller Upgrades <sup>2</sup>	PROC	Programmed				\$306,611		\$306,611
SFMTA	SFgo Controller Upgrades	PROC	Programmed					\$500,000	\$500,000
	Intelligent Transportation SFMTA Systems - Variable Message Signs <sup>1</sup>	CON	Pending				\$1,000,000		\$1,000,000
	Intelligent Transportation SFMTA Systems - Traffic Camera Deployment <sup>2</sup>	CON	Pending				\$1,200,000		\$1,200,000
		Total Pro	Total Programmed in 5YPP	0\$	0\$	0\$	\$2,506,611	\$500,000	\$3,006,611
1	Total	Allocated and	Total Allocated and Pending in 5YPPs	0\$	0\$	0\$	0\$	0\$	0\$
		Total Dec	Total Deobligated in 5YPPs	0\$	0\$	0\$	0\$	0\$	0\$
1 1		Total Una	Total Unallocated in 5YPPs	0\$	\$0	0\$	\$2,506,611	\$500,000	\$3,006,611
1	Total Pro	ogrammed in	Total Programmed in 2014 Strategic Plan	0\$	\$2,000,000	0\$	\$506,611	\$500,000	\$3,006,611
	Deobl	igated from Pı	Deobligated from Prior 5YPP Cycles *	\$8,000					\$8,000
	Cumulative Re	maining Prog	Cumulative Remaining Programming Capacity	\$8,000	\$2,008,000	\$2,008,000	\$8,000	\$8,000	\$8,000

\* "Deobligated from prior 5YPP cycles" includes deobligations from allocations approved prior to the current 5YPP period.

Programmed
Pending Allocation/Appropriation
Board Approved Allocation/Appropriation

### FOOTNOTES:

SFgo Controller Upgrades: Reduced from \$2,000,000 to \$1,000,000 in Fiscal Year 2015/16. Funds not needed because controller upgrades will be purchased using other 5YPP Amendment to accommodate allocation of Intelligent Transportation Systems - Variable Message Signs project (Res. Xx-xxxx, XX/XX/2018). capital project funds.

Intelligent Transportation Systems - Variable Message Signs: Added project with \$1,000,000 in FY 2018/19 for construction. <sup>2</sup> 5YPP Amendment to fund Intelligent Transportation Systems - Traffic Camera Deployment (Resolution XXX)

SFgo Controller Upgrades: Reduced from \$1,000,000 to \$0 in Fiscal Year 2015/16 and from \$506,611 to \$306,611 in Fiscal Year 2017/18. Intelligent Transportation Systems - Traffic Camera Deployment: Added project with \$1,200,000 in FY 2017/18 for construction.

Prop K 5-Year Project List (FY 2014/15 - 2018/19)
Advanced Technology and Information Systems (SFgo) (EP 32)
Cash Flow (\$) Maximum Annual Reimbursement
Pending March 20, 2018 Board

					Fiscal Year				
Project Name	Phase	2014/15	2015/16	2016/17	2017/18	2018/19	2019/20	2020/21	Total
SFgo Controller Upgrades1,2	PROC		0\$	0\$	0\$				0\$
SFgo Controller Upgrades2	PROC				\$53,306	\$253,305			\$306,611
SFgo Controller Upgrades	PROC						\$250,000	\$250,000	\$500,000
Intelligent Transportation Systems - Variable Message Signs1	CON				\$100,000	\$900,000			\$1,000,000
Intelligent Transportation Systems - Traffic Camera Deployment2	CON				\$200,000	\$1,000,000			\$1,200,000
Total C	Total Cash Flow in 5YPP	\$0	0\$	0\$	\$353,306	\$2,153,305	\$250,000	\$250,000	\$3,006,611
Total Cash	Total Cash Flow Allocated	0\$	0\$	0\$	0\$	0\$	0\$	0\$	0\$
Total Cash Fl	Total Cash Flow Deobligated	0\$	0\$	\$0	0\$	0\$	0\$	0\$	\$0
Total Cash Fl	Total Cash Flow Unallocated	\$0	80	80	\$353,306	\$2,153,305	\$250,000	\$250,000	\$3,006,611
Total Cash Flow in 2014 Strategic Plan	2014 Strategic Plan	0\$	\$666,666	\$666,667	\$919,973	\$253,305	\$250,000	\$250,000	\$3,006,611
Deobligated from Prior 5YPP Cycles *	r 5YPP Cycles *	\$8,000							\$8,000
Cumulative Remaining Cash Flow Capacity	ash Flow Capacity	\$8,000	\$674,666	\$1,341,333	\$1,908,000	\$8,000	\$8,000	\$8,000	\$8,000

<sup>\* &</sup>quot;Deobligated from prior 5YPP cycles" includes deobligations from allocations approved prior to the current 5YPP period.

Programmed
Pending Allocation/Appropriation
Board Approved Allocation/Appropriation

Table 3 - Prioritization Criteria and Scoring Table Advanced Technology and Information Systems (SFgo) (EP 32)

	PROP K P	PROP K PROGRAM-WIDE CRITERIA	CRITERIA	CATEG	CATEGORY SPECIFIC CRITERIA	ITERIA	
	Project Readiness	Community Support	Time Sensitive Urgency	Safety	Provides Benefits to Multiple Users	Muni Rapid Network	Total
Total Possible Score	4	3	3	4	3	3	20
SFgo Controller Upgrades		Locations will be so	cored at the time of al	location. See text for	Locations will be scored at the time of allocation. See text for details and appendix for a prioritized list	or a prioritized list.	
Intelligent Transportation Systems - Variable Message Signs	4	0	1	4	3	3	15
Intelligent Transportation Systems - Traffic Camera Deployment	4	0	1	4	3	3	15

## Prioritization Criteria Definitions:

detail and certainty for a project about to enter construction than design); whether prior project phases are completed or expected to be completed before beginning the next phase; and whether litigation, community Project Readiness: Project likely to need funding in fiscal year proposed. Factors to be considered include adequacy of scope, schedule, budget and funding plan relative to current project status (e.g. expect more opposition or other factors may significantly delay project.

Community Support: Project has clear and diverse community support and/or was it identified through a community-based planning process. An example of a community-based plan is a neighborhood transportation plan, but not a countywide plan or agency capital improvement program.

Three points for a project in an adopted community based plan with evidence of diverse community support. Two points for a project with evidence of support from both neighborhood stakeholders and groups and citywide groups.

1 wo points for a project with evidence of support from both neighborhood stakeholders and groups and citywide groups. One point for a project with evidence of support from either neighborhood stakeholders and groups or citywide groups. Time Sensitive Urgency: Project needs to proceed in proposed timeframe to enable construction coordination with another project (e.g., minimize costs and construction impacts); to support another funded or proposed project (e.g. new signal controllers need to be installed to support TEP implementation); or to meet timely use of funds deadlines associated with matching funds.

Safety: Project is located on a WalkFirst Safety Streets corridor (four points) or allows for a signal upgrade (e.g., pedestrian countdown signals) (two points).

Provides Benefits to Multiple Users: Projects receives one point each for addressing the needs of pedestrians, bicyclists, and/or transit users.

Muni Rapid Network: Project is located on the Muni Rapid Network.



This Page Intentionally Left Blank

FY of Allocation Action: 2017/18

Project Name: Intelligent Transportation Systems - Traffic Camera Deployment

Grant Recipient: San Francisco Municipal Transportation Agency - DPT

### **EXPENDITURE PLAN INFORMATION**

Prop K EP category: Advanced Technology and Information Systems (SFgo): (EP-32)

Prop K EP Line Number (Primary): 32 **Prop K Other EP Line Numbers:** 

Current Prop K Request: \$

1,200,000

Supervisorial District(s): Citywide

### REQUEST

### **Brief Project Description (type below)**

Purchase and deployment of closed-circuit television (CCTV) traffic cameras and related hardware at various locations throughout the city. CCTV traffic cameras are used by the Transportation Management Center to monitor traffic conditions and properly dispatch parking control officers, transit supervisors, and traffic signal electricians as needed. CCTV traffic cameras are also used by traffic engineers to evaluate traffic signal timing to better accomodate the various modes of travel.

### Detailed Scope, Project Benefits and Community Outreach (type below)

Prop K funds will be used to purchase and deploy Intelligent Transportation Systems (ITS) equipment such as: closed-circuit television (CCTV) traffic cameras and other related hardware (purchase includes extended warranty). CCTV traffic cameras will be implemented across 138 new locations to monitor field conditions for all modes of travel. The camera installation locations and the amount of locations may change if future needs change. See attached list of current and potential camera locations.

SFMTA currently has 84 traffic cameras in the field. The current and future selected camera locations are based on factors such as (1) fiber optic network presence, (2) roadway type classification (e.g. major and minor arterial roads), (3) Muni Rapid Network route, (4) Muni Stations, (5) locations near large crowd gatherings for special events, and (6) replacements for legacy cameras reaching end of service life.

Expanding the traffic camera network will provide tools to improve decision making and better manage field operations. Video camera footage is not recorded per city policy and will be monitored by (1) Transportation Management Center (TMC) staff to monitor field conditions and properly dispatch personnel (parking control officers, transit supervisors, traffic signal electricians) if the need arises; and (2) traffic engineers to evaluate traffic signal timing to better accommodate the various modes of travel.

We currently have 110 cameras in stock but need additional parts and labor to install them in the field. Once the current camera stock is depleted, we will buy as many as 160 additional cameras for deployment as described above. Traffic cameras are mounted on traffic signals, Muni overhead, or streetlight poles.

### Implementation:

SFMTA Sustainable Streets will manage the issuance and administration of purchase orders to purchase CCTV related equipment. Staff time will be allotted for CCTV and CCTV related installation and to ensure proper testing of the equipment so that it is compatible with the city's existing IT network. Department of Technology staff will evaluate fiber optic network availability at selected locations and provide fiber or radio connectivity to the intersections without fiber optic network availability.

Project Location (type below)
See the attached map for the camera locations.
Project Phase (select dropdown below)
Construction (CON)
Map or Drawings Attached? Yes
Other Items Attached? No
5YPP/STRATEGIC PLAN INFORMATION
Type of Project in the Prop K  5YPP/Prop AA Strategic Plan?  New Project
Diseas describe and institutes reseason, amondment.

Please describe and justify the necessary amendment:

To fund this request, the SFMTA is requesting an amendment to the Advanced Technology and Information Systems 5YPP to reprogram \$1,200,000 from the SFgo Controller Upgrades procurement placeholders to the subject project. Controller upgrades will be purchased using non-Prop K project funds.

Project Name: Intelligent Transportation Systems - Traffic Camera Deployment

### **ENVIRONMENTAL CLEARANCE**

**Environmental Type**: Categorically Exempt

### PROJECT DELIVERY MILESTONES

Enter dates below for ALL project phases, not just for the current request, based on the best information available. For PLANNING requests, please only enter the schedule information for the PLANNING phase.

Phase	S	tart	End		
Filase	Quarter	Calendar Year	Quarter	Calendar Year	
Planning/Conceptual Engineering (PLAN)					
Environmental Studies (PA&ED)			Jul-Sep	2008	
Right-of-Way					
Design Engineering (PS&E)					
Advertise Construction					
Start Construction (e.g. Award Contract)	Apr-Jun	2018			
Operations (i.e., paratransit)					
Open for Use			Apr-Jun	2019	
Project Completion (means last eligible expenditure)			Oct-Dec	2019	

### SCHEDULE DETAILS

Provide dates for any COMMUNITY OUTREACH planned during the requested phase(s). Identify PROJECT COORDINATION with other projects in the area (e.g. paving, MUNI Forward) and relevant milestone dates (e.g. design needs to be done by DATE to meet paving schedule). List any timely use-of-funds deadlines (e.g. federal obligation deadline). If a project is comprised of MULTIPLE SUB-PROJECTS, provide milestones for each sub-project. For PLANNING EFFORTS, provide start/end dates for each task.

Project Name: Intelligent Transportation Systems - Traffic Camera Deployment

### **FUNDING PLAN - FOR CURRENT REQUEST**

Enter the funding plan for the phase(s) that are the subject of the CURRENT REQUEST. Totals should match those shown in the Cost Summary below.

Fund Source		Planned	Pro	ogrammed	Allocated		Total
Prop K	\$	1,200,000	\$	-	\$	-	\$ 1,200,000
Prop 1B Bond	\$	-	\$	-	\$	550,000	\$ 550,000
	\$	-	\$	-	\$	-	\$ -
Total	: \$	1,200,000	\$	-	\$	550,000	\$ 1,750,000

### FUNDING PLAN - FOR ENTIRE PROJECT (ALL PHASES)

Enter the funding plan for all phases (planning through construction) of the project. This section may be left blank if the current request covers all project phases. Totals should match those shown in the Cost Summary below.

Fund Source	Planned	Pre	ogrammed	4	llocated	Total
Prop K	\$ 1,200,000	\$	=	\$	-	\$ 1,200,000
Prop 1B Bond	\$ -	\$	-	\$	600,000	\$ 600,000
	\$ -	\$	=	\$	-	\$ -
Total:	\$ 1,200,000	\$	-	\$	600,000	\$ 1,800,000

### COST SUMMARY

Show total cost for ALL project phases (in year of expenditure dollars) based on best available information. Source of cost estimate (e.g. 35% design, vendor quote) is intended to help gauge the quality of the cost estimate, which should improve in reliability the farther along a project is in its development.

Phase	Total Cost	Prop K - Current Request	Prop AA - Current Request	Source of Cost Estimate
Planning/Conceptual Engineering (PLAN)	\$ 20,000	N/A		Actual Cost
Environmental Studies (PA&ED)	\$ 10,000	N/A		Actual Cost
Right-of-Way	N/A	N/A		
Design Engineering (PS&E)	\$ 20,000	N/A	\$ -	Actual Cost
Construction (CON)	\$ 1,750,000	\$ 1,200,000	\$ -	Engineers Estimate at 100% design
Operations				
(Paratransit)	\$ -	\$ -		
Total:	\$ 1,800,000	\$ 1,200,000	\$ -	

% Complete of Design:	100%	as of	12/31/2017
<b>Expected Useful Life:</b>	15	Years	

Project Name: Intelligent Transportation Systems - Traffic Camera Deployment

## MAJOR LINE ITEM BUDGET

### CONSTRUCTION

SUMMARY BY MAJOR LINE ITEM (BY AGENCY LABO	LABOR BY TASK)					
Budget Line Item	Totals	% of contract	SFPW/DT	SFMTA	Con	Contractor
Construction	\$ 1,749,500	<b>%001</b>	100,000	\$ 1,149,500	\$	500,000
Contract Costs - Purchase Orders	\$ 500,000	<b>767</b>			s	500,000
Cameras (\$2,000 per camera)	\$ 380,000	%77			\$	380,000
Mounting Equipment	\$ 20,000	%1			\$	20,000
Cabling	\$ 20,000	1%			\$	20,000
Networking Equipment	\$ 80,000	%9			\$	80,000
Labor	\$ 974,550	<b>%9</b> 9		\$ 974,550		
Signal Shop Support - Installation costs						
dependent on the type of labor required at each						
location, can run from \$1,500 to \$4,000 per						
intersection.	\$ 774,550	44%		\$ 774,550		
Engineering Project Management	\$ 200,000	11%		\$ 200,000		
Work Authorizations to DT	\$ 100,000	<b>%9</b>	100,000			
Contingency	\$ 174,950	40%		\$ 174,950		

City Attorney Fees (for allocation)	\$	200
Phase Grand Total (Contract Costs+Labor+Work	¥	1 750 000
Authorizations+Contingency+City Attorney)	<del>)</del>	1,7,00,000

### TRANSPORTATION AUTHORITY RECOMMENDATION

This section is to be completed by Transportation Authority Staff.	

Res. Date:

Res. No: Project Name: Intelligent Transportation Systems - Traffic Camera Deployment

Grant Recipient: San Francisco Municipal Transportation Agency - DPT

**Funding** Recommended:

Action	Amount	Phase
Prop K	¢ 4 200 000	Construction (CON)
Allocation	\$ 1,200,000	Construction (CON)
Total:	\$ 1,200,000	

Total Prop K Funds: \$ 1,200,000 Total Prop AA Funds: \$

Eligible expenses must be incurred prior **Fund Expiration Date:** 6/30/2020 to this date.

### **Deliverables:**

**Last Updated:** 2/21/2018

1. Quarterly progress reports (QPRs) shall include the number and locations of CCTV traffic cameras that have been purchased or deployed and the percent complete for the overall project, in addition to the standard requirements for QPRs. See Standard Grant Agreement for details.

### **Special Conditions:**

- 1. The recommended allocation is contingent upon an amendment to the Advanced Technology and Information Systems 5YPP. See attached 5YPP amendment for details.
- 2. The Transportation Authority will only reimburse SFMTA up to the approved overhead multiplier rate for the fiscal year that SFMTA incurs charges.

### Notes:

1. Reminder: Prop K decals are required on equipment purchased with Prop K funds. See Standard Grant Agreement for details.

Metric	Prop K	Prop AA
Actual Leveraging - Current Request	31.43%	No Prop AA
Actual Leveraging - This Project	33.33%	No Prop AA

SFCTA Project	P&PD
Reviewer:	

### TRANSPORTATION AUTHORITY RECOMMENDATION

This section is to be completed by Transportation Authority Staff.

**Last Updated:** 2/21/2018 Res. No: Res. Date:

Project Name: Intelligent Transportation Systems - Traffic Camera Deployment

Grant Recipient: San Francisco Municipal Transportation Agency - DPT

SGA PROJECT NUMBER

Sponsor: San Francisco Municipal Transportation Agency - DPT

Intelligent Transportation Systems - Traffic Camera **SGA Project Number:** 132-9007XXX Name:

Deployment

Construction (CON) **Fund Share:** Phase: 68.57% Cash Flow Distribution Schedule by Fiscal Year **Fund Source** FY 2017/18 | FY 2018/19 | FY 2016/17 FY 2019/20 FY 2020/21+ **Total** Prop K \$200,000 \$ 1,000,000 \$1,200,000

Project Name: Intelligent Transportation Systems - Traffic Camera Deployment

Grant Recipient: San Francisco Municipal Transportation Agency - DPT

1) The requested sales tax and/or vehicle registration fee revenues will be used to supplement and under no circumstance replace existing local revenues used for transportation purposes.

Required for Allocation Request Form Submission
Initials of sponsor staff member verifying the above statement

TM

	CONTACT	TINFORMATION
	Project Manager	Grants Section Contact
Name:	Ramon Zamora	Tim Manglicmot
Title:	Engineer	Acting Manager, Capital Procurement & Mana
Phone:	415-701-5668	415-646-2517
Email:	Ramon.Zamora@sfmta.com	Timonthy.Manglicmot@sfmta.com

Scale 1:17,000
Date Saved: 1/23/2018
For relevence contact. Ramic Created by: Edward Tang

### MAPS AND DRAWINGS

There are 138 identified locations for future CCTV installation. Installation locations will be based on feedback from Transit Division, Sustainable Streets - Engineering & Enforcement. Future - Currently Nonsignalized (5) - MUNI Metro & Rapid Routes Awaiting Construction (22) Existing-Legacy (12) - Non-Rapid Routes SFgo CCTV Map - Express Routes **MUNI Network** Existing (72) Future (138) **CCTV Status** January 2018

Status

Existing

Existing

1,4,5

20

15

Awaiting Construction

## San Francisco County Transportation Authority Prop K/Prop AA Allocation Request Form

SFgo CCTV Status by Intersection

ģ

Districts EL CAMINO DEL MA **EMBARCADERO** CASTRO CROSS OVER EUCALYPTUS Street2 FELL HARRISON HOWARD BRYANT HARRISON HOLLOWAY MISSION DUBOCE CHURCH MISSION TAYLOR BRYANT GEARY Street1 25TH ST 30TH AVE 30TH ST 32ND AVE 33RD AVE 36TH AVE 48TH AVE ALEMANY 17TH ST 19TH AVE 20TH ST 23RD ST 24TH ST 09TH AVE 09TH AVE 09TH AVE 09TH ST 25TH AVE 25TH AVE BATTERY BATTERY 10TH ST 10TH ST 10TH ST 11TH ST 11TH ST 11TH ST BATTERY 13TH ST 14TH ST 16TH ST 16TH ST 16TH ST **STH ST** 10TH ST 12TH ST 24TH ST 110 BAY 58 60 60 62 63 63 64 65 66 66 67 68 70 72 73 75 9/ 22 79 80 81 82 83 84 85 87 88 89 90 92 94 95 86 99 100 101 103 104 96 26 26 Awaiting Construction Status xisting Existing Existing Existing Existing Existing Existing Future Future Future Future Future Districts 6,10 3,6 10 9 10 9 9 **ERRY FRANCOIS** RAMP Street2 JAMESTOWN CALIFORNIA FULTON JS 101 OFF CHANNEL EVANS FOLSOM HOWARD 16TH ST 20TH ST 25TH ST BAYVIEW BRYANT **3RANNAN** BATTERY FOLSOM **3RANNAN** MISSION 16TH ST BRYANT MARKET FULTON MENDEL Street1
01ST ST
01ST ST
01ST ST
01ST ST
02ND ST
02ND ST
02ND ST
02ND ST
02ND ST
03ND ST
03ND ST 06TH AVE 06TH AVE 06TH ST 06TH ST 06TH ST 33RD ST 33RD ST 33RD ST 33RD ST 33RD ST 33RD ST 3RD ST 3RD ST 3RD ST 3RD ST 04TH ST 05TH ST 05TH ST 3RD ST 3RD ST

Construction

34

35 36

59

39 41 42

Existing

Sonstruction

1,2

48

49

22

24

44 45 46

43

an Francisco County Transportation Authority Prop K/Prop AA Allocation Request Form
--

Ctatus	2	Ctrootd	C+0043	Diotrioto	Stotus
Status	NO.	Street	Streetz	DISTRICTS	Status
oldine Scittis	160		LOIMION	7 (	Futuro
Existing	170	FOI SOM	FREMONT	6	Future
Figure	171	FOREST HILL STA	AGIINA HONDA	2	Future
Future	172	FRANCISCO	RICHARDSON	, 0	Fiftire
Future	173	FRANKI IN	GEARY	2.5	Fxisting
Existing	174	FRANKLIN	GOI DEN GATE		Fittire
Future	175	FRANKLIN	LOMBARD	2	Existing
Future	176	FRANKLIN	OAK	2	Existing
Future	177	FRANKLIN	SUTTER	2	Future
Future	178	FREMONT	MISSION	9	Existing
Future	179	FULTON	GREAT HIGHWAY	1	Future
Awaiting Construction	180	FULTON	PARK PRESIDIO	1	Existing
Future	181	FULTON	PARKER	1	Future
Future	182	FULTON	STANYAN	1	Existing
Existing	183	GEARY	вопен	2,5	Existing
Future	184	GEARY	MASONIC	1,2	Awaiting Construction
Future	185	GEARY	PARK PRESIDIO	1	Existing
Future	186	GEARY	POWELL	3	Future
Future	187	GEARY	STOCKTON	3	Future
Awaiting Construction	188	GEARY	VAN NESS	5,6	Awaiting Construction
Future	189	GENEVA	MISSION	11	Existing
Future	190	GENEVA	MOSCOW	11	Future
Future	191	GENEVA	OCEAN	7,11	Future
Future	192	GENEVA	SAN JOSE	11	Future
Existing	193	GOLDEN GATE	LEAVENWORTH	9	Future
Future	194	GORGAS	LYON	2	Future
Future	195	вой	HAIGHT	5,6	Future
Future	196	GOUGH	JACKSON	7 0	Existing
ruure	197	90091	SACRAIMEINIO	7 1	Existing
ainin	190	GOOGH	I NOON	0 1	Existing
Lature	661	GREAT TWT	LINCOLIN	1,4	e inina
ainin	200	T WILL TAINS	MASONIC	4,7	ainna
Future	202	HARRISON	MAIN	0	Future
Future	202	HAYES	VAN NESS	5.6	Awaiting Construction
Future	203	HOWARD	MAIN	ر د	
Future	205	HOWARD	SPEAR	9	Future
Future	206	JEFFERSON	TAYLOR	n (C)	Future
Future	207	JOHN F KENNEDY	STANYAN	1,5	Existing
Future	208		MARKET	9	Awaiting Construction
Future	209	JUDAH	SUNSET	4	Future
Future	210	JUNIPERO SERRA	PORTOLA	7	Future
Existing	211	KEARNY	PINE	3	Future
Future	212	LAGUNA	MARINA	2	Future
Future	213	LAKE	PARK PRESIDIO	1,2	Future
Awaiting Construction	214	LARKIN	MCALLISTER	9	Future
Future	215	LOMBARD	VAN NESS	2	Awaiting Construction
Future	216	MAIN	MISSION	9	Existing
Future	217	MARIPOSA	US I-280 OFF RAMF	6,10	Future
Existing	218	MARKET	MIDBLOCK AT	3,6	Existing
Existing	219	MARKET	OCTAVIA	5,6,8	Existing
Future	220	MARKET	SANSOME	3,6	Existing
Existing	221	MARKET	SOUTH VAN NESS	5,6	Awaiting Construction
Future	222		OAK	5	Existing
Future	223	TER	VAN NESS	5,6	Awaiting Construction
-uture	224	MISSION	PERSIA	11	Existing

No.	Street1	Street2	Districts	Status
111	BAYSHORE	CORTLAND	9,10	Future
112	BAYSHORE	SUNNYDALE	10	Existing
113	BAYSHORE	VISITACION	10	Future
114	BEACH	EMBARCADERO	3	Future
115	BEACH	HYDE	2	Future
116	BEACH	JONES	3	Future
117	BEALE	DAVIS	3,6	Existina
118	BEALE	HOWARD	9	Future
119	BOSWORTH	DIAMOND	8	Future
120	BROADWAY	COLUMBUS	3	Future
121	BROADWAY	EMBARCADERO	3	Future
122	BROADWAY	POWELL	3	Future
123	BROADWAY	VAN NESS	2.3	Awaiting Construction
124	BRODERICK	LOMBARD	5	
125	BROTHERHOOD	LAKE MERCED	7	Future
126	BRYANT	EMBARCADERO	9	Existing
127	BUSH	FRANKLIN	2	Future
128	BUSH	STOCKTON	3	Future
129	CALIFORNIA	DAVIS	3	Future
130	CALIFORNIA	DRUMM	3	Future
131	CALIFORNIA	VAN NESS	2.3	Awaiting Construction
132	CARTER	GENEVA	11	
133	CERVANTES	MARINA	2	Future
134	CESAR CHAVEZ	FVANS	10	Future
135	CESAR CHAVEZ	KANSAS	10	Future
136	CESAR CHAVEZ	MISSION	<u>6</u>	Existing
137	CESAR CHAVEZ	VAI FNCIA	σα	Fithire
138	CHESTALIT	COLLIMBIE	G, 0	Figure
130	CHECTNIT	EMBABOADEDO	0 0	- didie
139	CHESTING		0 0	a minu
140	CHESTING	FILLINDRE	7 0	rulure F. f
141	CLAY	DRUMINI TRANSPINI	n (	Future
142	CLAY	P-KANKLIN 04001401	7	Future
143	CLAY	SIOCKION	ۍ ر	Future
144	COLUMBUS	KEAKNY	3	Future
145	COLUMBUS	MONTGOMERY	3	Future
146	COLUMBUS	UNION	3	Future
147	DEWEY	LAGUNA HONDA	7	Future
148	DIAMOND	MONTEREY	8	Future
149	DIVISADERO	FELL	2	Future
150	DIVISADERO	GEARY	2	Future
151	DIVISADERO	SUTTER	2.5	Future
152	DOLORES	RANDALL	8.9	Future
153	DON CHEE	EMBARCADERO	c	Future
154	DRUMM	MAIN	3.6	Existina
155	DRIMM	MIDRI OCK AT	ď	Fittire
156	DWIGHT	PALII	o o	Future
157	FDDY	NAN NESS	94	Awaiting Construction
158	FMRARCADERO	FOI SOM	95	Future
159	EMBARCADERO	IFFFFRSON	o m	Future
160	FMBARCADERO	KEARNY	o e	Future
161	FMBARCADERO	KING	9	Existing
162	FMBARCADERO	MIDBI OCK AT	o en	Existing
163	FEI I		o w	Fittire
16.1	בבוו	רוביונים וכיי	ס ע	Figure
104	רבור	GOOGH	Ω L	Existing
165	FELL	MASONIC	5	Future
166	FELL	OCTAVIA	5	Future
167	FILLMORE	GEARY	5	Future

No.	Street1	Street2	Districts	Status
225	MISSION	SILVER	11	Existing
226	MISSION	STEUART	3,6	Existing
227	MONTGOMERY	SACRAMENTO	3	Future
228	OAK	OCTAVIA	2	Existing
229	OCEAN	ON RAMP I-280	11	Future
230	OCEAN	SAN JOSE	11	Future
231	O'FARRELL	VAN NESS	5,6	Awaiting Construction
232	O'SHAUGHNESS\ PORTOLA	PORTOLA	7,8	Future
233	PHELAN	MIDBLOCK AT	7	Existing
234	PINE	VAN NESS	2,3	Awaiting Construction
235	PLYMOUTH	SAGAMORE	11	Future
236	POST	POWELL	3	Future
237	POST	STOCKTON	3	Future
238	POST	VAN NESS	2,3,5	Awaiting Construction
239	POWELL	SACRAMENTO	3	Future
240	SAN BRUNO	SILVER	6	Future
241	SANSOME	WASHINGTON	3	Future
242	STOCKTON	SUTTER	3	Future
243	SUNSET	TARAVAL	4	Future
244	244 UNION	VAN NESS	2,3	Awaiting Construction

Existing: Locations with existing traffic cameras.

Awaiting Construction: Intersections identified for traffic camera deployment that are awaiting construction work to finish (e.g. Van Ness Corridor)

Future: Intersections being considered for traffic camera deployment.

# Prop K 5-Year Project List (FY 2014/15 - 2018/19) Advanced Technology and Information Systems (SFgo) (EP 32) Programming and Allocations to Date

8 Board
201
20,
<b>[arch</b>
2
nding

	9 Total	0\$	\$306,611	000 \$200,000	\$1,000,000	\$1,200,000	,000 \$3,006,611	0\$	0\$	,000 \$3,006,611	,000 \$3,006,611	\$8,000	\$8,000
	2018/19			\$500,000			\$500,000			\$500,000	\$500,000		
	2017/18		\$306,611		\$1,000,000	\$1,200,000	\$2,506,611	0\$	0\$	\$2,506,611	\$506,611		\$8,000
Fiscal Year	2016/17						0\$	0\$	0\$	0\$	0\$		\$2,008,000
	2015/16	0\$					0\$	0\$	0\$	0\$	\$2,000,000		\$2,008,000
	2014/15						\$	\$0	0\$	\$0	\$	\$8,000	\$8,000
	Status	Programmed	Programmed	Programmed	Pending	Pending	Total Programmed in 5YPP	Total Allocated and Pending in 5YPPs	Total Deobligated in 5YPPs	Total Unallocated in 5YPPs	Total Programmed in 2014 Strategic Plan	Deobligated from Prior 5YPP Cycles *	Cumulative Remaining Programming Capacity
	Phase(s)	PROC	PROC	PROC	CON	NOO	Total Pro	Allocated and	Total Dec	Total Una	grammed in	igated from P	maining Prog
	Project Name	SFMTA SFgo Controller Upgrades 1,2	SFMTA SFgo Controller Upgrades <sup>2</sup>	SFMTA SFgo Controller Upgrades	SFMTA Systems - Variable Message Signs <sup>1</sup>	Intelligent Transportation SFMTA Systems - Traffic Camera Deployment <sup>2</sup>		Total			Total Pro	Deobl	Cumulative Re
	Agency	SFMTA	SFMTA	SFMTA	SFMTA	SFMTA							

\* "Deobligated from prior 5YPP cycles" includes deobligations from allocations approved prior to the current 5YPP period.

Programmed
Pending Allocation/Appropriation
Board Approved Allocation/Appropriation

### FOOTNOTES:

SFgo Controller Upgrades: Reduced from \$2,000,000 to \$1,000,000 in Fiscal Year 2015/16. Funds not needed because controller upgrades will be purchased using other 5YPP Amendment to accommodate allocation of Intelligent Transportation Systems - Variable Message Signs project (Res. Xx-xxxx, XX/XX/2018). capital project funds.

Intelligent Transportation Systems - Variable Message Signs: Added project with \$1,000,000 in FY 2018/19 for construction.

SFgo Controller Upgrades: Reduced from \$1,000,000 to \$0 in Fiscal Year 2015/16 and from \$506,611 to \$306,611 in Fiscal Year 2017/18. Intelligent Transportation Systems - Traffic Camera Deployment: Added project with \$1,200,000 in FY 2017/18 for construction. <sup>2</sup> 5YPP Amendment to fund Intelligent Transportation Systems - Traffic Camera Deployment (Resolution XXX)

Prop K 5-Year Project List (FY 2014/15 - 2018/19)
Advanced Technology and Information Systems (SFgo) (EP 32)
Cash Flow (\$) Maximum Annual Reimbursement
Pending March 20, 2018 Board

			Suppris 1	Hierarchical Colonial Hierarchical	Fiscal Vear				
Project Name	Phase	2014/15	2015/16	2016/17	2017/18	2018/19	2019/20	2020/21	Total
SFgo Controller Upgrades1,2	PROC		0\$	0\$	0\$				0\$
SFgo Controller Upgrades2	PROC				\$53,306	\$253,305			\$306,611
SFgo Controller Upgrades	PROC						\$250,000	\$250,000	\$500,000
Intelligent Transportation Systems - Variable Message Signs1	NOO				\$100,000	\$900,000			\$1,000,000
Intelligent Transportation Systems - Traffic Camera Deployment2	CON				\$200,000	\$1,000,000			\$1,200,000
Total C	Total Cash Flow in 5YPP	0\$	\$0	0\$	\$353,306	\$2,153,305	\$250,000	\$250,000	\$3,006,611
Total Cash	Total Cash Flow Allocated	0\$	0\$	0\$	0\$	0\$	\$0	\$0	\$0
Total Cash Fl	Total Cash Flow Deobligated	0\$	0\$	0\$	0\$	0\$	\$0	\$0	0\$
Total Cash Fl	Total Cash Flow Unallocated	\$0	0\$	0\$	\$353,306	\$2,153,305	\$250,000	\$250,000	\$3,006,611
Total Cash Flow in 2014 Strategic	2014 Strategic Plan	0\$	\$666,666	\$666,667	\$919,973	\$253,305	\$250,000	\$250,000	\$3,006,611
Deobligated from Prior 5YPP Cycles *	r 5YPP Cycles *	\$8,000							\$8,000
Cumulative Remaining Cash Flow Capacity	ash Flow Capacity	\$8,000	\$674,666	\$1,341,333	\$1,908,000	\$8,000	\$8,000	\$8,000	\$8,000

<sup>\* &</sup>quot;Deobligated from prior 5YPP cycles" includes deobligations from allocations approved prior to the current 5YPP period.

Programmed
Pending Allocation/Appropriation
Board Approved Allocation/Appropriation

# Table 3 - Prioritization Criteria and Scoring Table Advanced Technology and Information Systems (SFgo) (EP 32)

	PROP K PRC	ROGRAM-WIDE CRITERIA	CRITERIA	CATEG	CATEGORY SPECIFIC CRITERIA	ITERIA	
	Project Readiness	Community Support	Time Sensitive Urgency	Safety	Provides Benefits to Multiple Users	Muni Rapid Network	Total
Total Possible Score	4	3	3	4	3	3	20
SFgo Controller Upgrades		Locations will be so	Locations will be scored at the time of allocation. See text for details and appendix for a prioritized list	location. See text for	details and appendix fo	or a prioritized list.	
Intelligent Transportation Systems - Variable Message Signs	4	0	1	4	3	3	15
Intelligent Transportation Systems - Traffic Camera Deployment	4	0	1	4	3	3	15

## Prioritization Criteria Definitions:

detail and certainty for a project about to enter construction than design); whether prior project phases are completed or expected to be completed before beginning the next phase; and whether litigation, community Project Readiness: Project likely to need funding in fiscal year proposed. Factors to be considered include adequacy of scope, schedule, budget and funding plan relative to current project status (e.g. expect more opposition or other factors may significantly delay project.

Community Support: Project has clear and diverse community support and/or was it identified through a community-based planning process. An example of a community-based plan is a neighborhood transportation plan, but not a countywide plan or agency capital improvement program.

Three points for a project in an adopted community based plan with evidence of diverse community support.

Two points for a project with evidence of support from both neighborhood stakeholders and groups and citywide groups.

I wo points for a project with evidence of support from both neighborhood stakeholders and groups and citywide groups. One point for a project with evidence of support from either neighborhood stakeholders and groups or citywide groups.

Time Sensitive Urgency: Project needs to proceed in proposed timeframe to enable construction coordination with another project (e.g., minimize costs and construction impacts); to support another funded or

proposed project (e.g. new signal controllers need to be installed to support TEP implementation); or to meet timely use of funds deadlines associated with matching funds.

Safety: Project is located on a WalkFirst Safety Streets corridor (four points) or allows for a signal upgrade (e.g., pedestrian countdown signals) (two points).

Provides Benefits to Multiple Users: Projects receives one point each for addressing the needs of pedestrians, bicyclists, and/or transit users.

Muni Rapid Network: Project is located on the Muni Rapid Network.



**This Page Intentionally Left Blank** 

FY of Allocation Action: 2017/18

**Project Name:** District 11 Near-Term Traffic Calming [NTIP Capital]

Grant Recipient: San Francisco Municipal Transportation Agency - DPT

### **EXPENDITURE PLAN INFORMATION**

Prop K EP category: Traffic Calming: (EP-38)

Prop K EP Line Number (Primary): 38 Current Prop K Request: \$ 600,000

Supervisorial District(s): District 11

### **REQUEST**

### **Brief Project Description (type below)**

Neighborhood Transportation Improvement Program (NTIP) Capital funds will be used to implement quick and effective near-term traffic calming measures at locations in District 11. Specific locations and improvement types will be determined in collaboration with the District 11 Supervisor's Office, and will be based on technical factors, such as feasibility and proximity to schools, as well as community input. Community outreach within the Excelsior is being conducted as part of the Excelsior Neighborhood Traffic Calming Planning Project and the Excelsior Neighborhood Strategy.

### **Detailed Scope, Project Benefits and Community Outreach (type below)**

See attached.

### **Project Location (type below)**

District 11

### Project Phase (select dropdown below)

Multiple Phases

Map or Drawings Attached? Yes

Other Items Attached? No

### **San Francisco County Transportation Authority** Prop K/Prop AA Allocation Request Form 5YPP/STRATEGIC PLAN INFORMATION

Type of Project in the Prop K 5YPP/Prop AA Strategic Plan?	Project Drawn From Placeholder	
Is the requested amount greater than the amount programmed in the relevant 5YPP or Strategic Plan?	Less than or Equal to Programmed Amount	
Prop K 5YPP Amount:	Prop AA \$ 970,000 Strategic Plan Amount:	

### San Francisco County Transportation Authority Proposition K Sales Tax Program Allocation Request Form

### Introduction

The San Francisco Municipal Transportation Agency (SFMTA) requests an allocation of \$600,000 in Prop K Neighborhood Transportation Improvement Program (NTIP) funds for the District 11 Near-Term Traffic Calming Project. This allocation will cover detailed design and construction of traffic calming devices and minor traffic modifications in District 11.

The Transportation Authority's NTIP is intended to strengthen project pipelines and advance the delivery of community-supported neighborhood-scale projects, especially in Communities of Concern and other neighborhoods with high unmet needs.

### Scope

The SFMTA will design and implement a suite of traffic calming and traffic safety modifications in District 11. The project budget details a sample mix of scoped improvements that would utilize the full project funding. The actual mix of improvements will be determined in collaboration with the Supervisor and the community. The budget could cover the following:

- 32 Speed humps or speed cushions
- 18 Upgraded intersections: after identifying top intersection needs, will consider a combination of the following measures as appropriate to the specific location:
  - o Painted Safety Zones
  - Raised Crosswalks
  - o High Visibility (Continental) marked crosswalks
  - o STOP or other traffic signs
- Other midblock or intersection improvements may be recommended, and cost estimates will be completed to determine potential trade-offs from the items noted above.

### **Final Project Selection**

The SFMTA will conduct the following steps in coordination with the Supervisors office to finalize the list of projects to be funded. For projects in the Excelsior district this work will be funded by the Excelsior Neighborhood Traffic Calming project.

- 1. The SFMTA has developed a draft list of potential projects in coordination with the Supervisor's office and through the outreach phase of the related Excelsior Neighborhood Traffic Calming Planning Project
- 2. SFMTA will confirm feasibility, cost, and timelines of identified potential projects and will group projects by priority. High priority will be given to:
  - a. Projects near schools and community assets
  - b. Projects with documented safety issues such as exhibition driving
  - c. Projects have documented community support
  - d. Projects that can be implemented quickly
- 3. SFMTA will share recommended list with Supervisor's office and seek confirmation on direction
- 4. SFMTA will share revised list with SFCTA as deliverable to release construction funding
- 5. Depending on the measure, final steps are needed for the project to be approved and implemented:
  - a. Balloting for speed humps on streets without schools
  - b. Public hearing posting for measures near schools and operational measures

### San Francisco County Transportation Authority Proposition K Sales Tax Program Allocation Request Form

While the final list of locations and measures is yet to be determined, several locations have risen to the top in terms of likely priority. These include improvements along corridors such as Naples Street, Vienna Street, Avalon Avenue, Orizaba Avenue, and Moscow Street with a focus on the intersection with Persia; near schools including Epiphany, Cleveland; and pedestrian access to Excelsior Playground, Balboa Park, McLaren Park, and Minnie and Lovey Ward Recreation center.

### Outreach

Community outreach for measures within the Excelsior is being conducted as part of partner projects, the Excelsior Neighborhood Traffic Calming Planning Project and the SF Planning Department's Excelsior Neighborhood Strategy, which include in-depth outreach to community groups, schools, faith-based institutions, advocacy groups, merchant associations, local social services recipients, and the general public.

Legislation for all project elements is included in the design phase for this project and will include balloting and public hearings for projects that require them per the SFMTA's standard processes; this will serve as the opportunity for community input as these projects are approved. Targeted outreach will be conducted for specific locations on an as needed basis.

### Schedule

Due to the nature of the projects included in this project, implementation of some projects may begin while detailed design continues for other elements. Therefore, the SFMTA requests concurrent access to funding from both phases. Construction funding will be made available as soon as SFMTA provides a revised project list that has been vetted through the District 11 Supervisors office.

Implementation of paint-only measures will begin as early as June 2018 while measures such as median islands and speed humps that require San Francisco Fire Department approval and Public Works coordination may not be implemented until the end of 2018.

### **Environmental Clearance**

Traffic calming measures proposed in this allocation request have been determined to be categorically exempt from CEQA review by the SFMTA Environmental Planning Team and the San Francisco Planning Department.

### **Prioritization**

Supervisor Safai has highlighted this project as a priority for his district and has designated this project for District 11 NTIP funds. Measures identified for inclusion in this request are those that can be implemented in a relatively short time frame appropriate to the project goals.

Project Name: District 11 Near-Term Traffic Calming [NTIP Capital]

### **ENVIRONMENTAL CLEARANCE**

**Environmental Type**: Categorically Exempt

### PROJECT DELIVERY MILESTONES

Enter dates below for ALL project phases, not just for the current request, based on the best information available. For PLANNING requests, please only enter the schedule information for the PLANNING phase.

Phase	S	tart	E	nd
Filase	Quarter	Calendar Year	Quarter	Calendar Year
Planning/Conceptual Engineering (PLAN)	Jul-Sep	2017	Oct-Dec	2018
Environmental Studies (PA&ED)				
Right-of-Way				
Design Engineering (PS&E)	Apr-Jun	2018	Oct-Dec	2018
Advertise Construction				
Start Construction (e.g. Award Contract)	Apr-Jun	2018		
Operations (i.e., paratransit)				
Open for Use			Oct-Dec	2018
Project Completion (means last eligible expenditure)			Oct-Dec	2018

### SCHEDULE DETAILS

Provide dates for any COMMUNITY OUTREACH planned during the requested phase(s). Identify PROJECT COORDINATION with other projects in the area (e.g. paving, MUNI Forward) and relevant milestone dates (e.g. design needs to be done by DATE to meet paving schedule). List any timely use-of-funds deadlines (e.g. federal obligation deadline). If a project is comprised of MULTIPLE SUB-PROJECTS, provide milestones for each sub-project. For PLANNING EFFORTS, provide start/end dates for each task.

Community Outreach and SFMTA Board legislation hearings: July 2017-December 2018 (early outreach has been conducted through CBTP Excelsior Traffic Calming Grant)

Design: April - December 2018

Construction: June - December 2018

Project Name: District 11 Near-Term Traffic Calming [NTIP Capital]

### FUNDING PLAN - FOR CURRENT REQUEST

Enter the funding plan for the phase(s) that are the subject of the CURRENT REQUEST. Totals should match those shown in the Cost Summary below.

Fund Source	Planned	Pro	grammed	Alloca	ted	Total
Prop K		\$	600,000	\$	-	\$ 600,000
SFMTA Operating	\$ -	\$	150,640	\$	-	\$ 150,640
Total:	\$ -	\$	750,640	\$		\$ 750,640

### **COST SUMMARY**

Show total cost for ALL project phases (in year of expenditure dollars) based on best available information. Source of cost estimate (e.g. 35% design, vendor quote) is intended to help gauge the quality of the cost estimate, which should improve in reliability the farther along a project is in its development.

Phase	То	tal Cost	C	Prop K - Current Request	Prop AA - Current Request	Source of Cost Estimate
Planning/Conceptual Engineering (PLAN)	\$	-	\$	-		
Environmental Studies (PA&ED)	\$	-				
Right-of-Way	\$	-	\$	-		
Design Engineering (PS&E)	\$	154,000	\$	100,000		
Construction (CON)	\$	596,640	\$	500,000		assumes full build-out of potential measures
Total:	\$	750,640	\$	600,000	\$ -	

% Complete of Design:	0%	as of	2/6/2018
<b>Expected Useful Life:</b>	35 Years		

### PROPOSED REIMBURSEMENT SCHEDULE FOR CURRENT REQUEST (instructions as noted below)

Use the table below to enter the proposed reimbursement schedule for the current request. Prop K and Prop AA policy assume these funds will not be reimbursed at a rate greater than their proportional share of the funding plan for the relevant phase unless justification is provided for a more aggressive reimbursement rate. If the current request is for multiple phases, please provide separate reimbursement schedules by phase. If the proposed schedule exceeds the years available, please attach a file with the requested information.

Phase:	Design Engine	eering (PS&E)				
Fund Source	FY 2017/18	FY 2018/19	FY 2019/20	FY 2020/21	FY 2021/22+	Total
Prop K	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Phase:	Construction (	(CON)				
Fund Source	FY 2017/18	FY 2018/19	FY 2019/20	FY 2020/21	FY 2021/22+	Total
Prop K	\$ 500,000	\$ -	\$ -	\$ -	\$ -	\$ 500,000

Project Name: District 11 Near-Term Traffic Calming [NTIP Capital]

## MAJOR LINE ITEM BUDGET

SUMMARY BY MAJOR LINE IT	TEM - DESIGN	
Budget Line Item	Totals	% of Phase
1. Total SFMTA Labor	\$ 140,000	
2. Contingency	14,000	10%
TOTAL PHASE	\$ 154,000	

MAJOR LINE	E ITEM BUDGET	MAJOR LINE ITEM BUDGET - CONSTRUCTION		
Expenses	Unit Cost	# of Units		Total
1.0 Data Collection				
-Speed Surveys	\$ 200	0 16	\$	8,000
-Counts	\$ 250	0 12	\$	3,000
		SUBTOTAL	ઝ	11,000
2.0 SFMTA Construction Work Orders	rders			
-Painted Safety Zones	\$ 6,000	0 12	s	72,000
-STOP or Advisory signs	\$ 800	0 24	s	19,200
- Striping, linear feet	\$ 3.20	0 17,500	s	56,000
-Continental Crosswalks (Each				
leg)	\$ 800	0 44	↔	35,200
		SUBTOTAL	\$	182,400
3.0 SFPW Construction Work Authorizations	uthorizations			
-Speed humps	\$ 7,000	0 32	s	224,000
-Raised crosswalks	10,000	8 0	\$	80,000
-Islands	15,000	0	\$	45,000
		SUBTOTAL	s	349,000
Contingency (10%)			ક્ર	54,240
		TOTAL	\$	596,640

This table represents a sample mix of scoped improvements that would utilize the full project funding. The actual mix of improvements will be determined in collaboration with the Supervisor and the community.

### TRANSPORTATION AUTHORITY RECOMMENDATION

### This section is to be completed by Transportation Authority Staff.

**Last Updated:** 2/20/2018 Res. Date: Res. No:

Project Name: District 11 Near-Term Traffic Calming [NTIP Capital]

Grant Recipient: San Francisco Municipal Transportation Agency - DPT

Funding
Recommended:

Action	Α	mount	Phase
Prop K Allocation	\$	100,000	Design Engineering (PS&E)
Prop K Allocation	\$	500,000	Construction (CON)
Total:	\$	600,000	

Total Prop K Funds: \$ 600.000 **Total Prop AA Funds: \$** 

Given strong interest by the sponsoring commissioner Justification for multi-phase in delivering the projects as quickly as possible, and recommendations and notes for the relatively straightforward design of similar multi-sponsor recommendations: improvements at multiple locations, we are recommending concurrent allocation of design and construction funds.

> Eligible expenses must be incurred prior **Fund Expiration Date:** 6/30/2019 to this date.

### **Deliverables:**

- 1. Quarterly progress reports shall provide summary of community feedback, details on improvements constructed in the previous guarter, improvements expected to be constructed in the following quarter, and overall progress in addition to the requirements specified in the Standard Grant Agreement.
- 2. With quarterly progress reports, provide 2-3 photos of before conditions and work being performed. Upon completion of improvements, provide 2-3 digital photos of completed work. 3.

### **Special Conditions:**

- 1. SFMTA may not incur expenses for the construction phase until Transportation Authority staff releases the funds (\$500,000) pending receipt of locations and measures as confirmed by the District supervisor.
- 2. The Transportation Authority will only reimburse SFMTA up to the approved overhead multiplier rate for the fiscal year that SFMTA incurs charges. 3.

### Notes:

1. The Transportation Authority will share quarterly progress reports with the District Supervisor for this NTIP project.

E7-92

### San Francisco County Transportation Authority Prop K/Prop AA Allocation Request Form TRANSPORTATION AUTHORITY RECOMMENDATION

This section is to be completed by Transportation Authority Staff.					
Last Updated:	2/20/2018	Res. No:	Res. Date:		
Project Name:	District 11 Nea	r-Term Traffic Cal	ming [NTIP Capital]		
Grant Recipient:	San Francisco Municipal Transportation Agency - DPT				
2.					

### TRANSPORTATION AUTHORITY RECOMMENDATION

### This section is to be completed by Transportation Authority Staff.

Last Updated: 2/20/2018 Res. No: \_\_\_\_\_ Res. Date: \_\_\_\_\_

Project Name: District 11 Near-Term Traffic Calming [NTIP Capital]

Grant Recipient: San Francisco Municipal Transportation Agency - DPT

Metric	Prop K	Prop AA
Actual Leveraging - Current Request	20.07%	No Prop AA
Actual Leveraging - This Project	20.07%	No Prop AA

SFCTA Project P&PD

Reviewer:

### SGA PROJECT NUMBER

Sponsor: San Francisco Municipal Transportation Agency - DPT

SGA Project Number: 138-xxxxxx Name: District 11 Near-Term Traffic Calming [NTIP Capital] - Design

Phase: Design Engineering (PS&E) Fund Share: 79.93%

Cash Flow Distribution Schedule by Fiscal Year

 Cash Flow Distribution Scriedule by Fiscal Year

 Fund Source
 FY 2017/18
 FY 2018/19
 FY 2019/20
 FY 2020/21
 FY 2021/22+
 Total

 Prop K
 \$100,000
 \$100,000
 \$100,000

Sponsor: San Francisco Municipal Transportation Agency - DPT

SGA Project Number: 138-xxxxxx Name: District 11 Near-Term Traffic Calming [NTIP Capital] - Construction

 Phase:
 Construction (CON)
 Fund Share:
 79.93%

 Cash Flow Distribution Schedule by Fiscal Year

 Fund Source
 FY 2017/18
 FY 2018/19
 FY 2019/20
 FY 2020/21
 FY 2021/22+
 Total

 Prop K
 \$500,000
 \$500,000
 \$500,000

FY of Allocation Action: 2017/18 Current Prop K Request: \$ 600,000

Project Name: District 11 Near-Term Traffic Calming [NTIP Capital]

Grant Recipient: San Francisco Municipal Transportation Agency - DPT

1) The requested sales tax and/or vehicle registration fee revenues will be used to supplement and under no circumstance replace existing local revenues used for transportation purposes.

Required for Allocation Request Form Submission
Initials of sponsor staff member verifying the above statement

### $\mathsf{TM}$

CONTACT INFORMATION					
	Project Manager	Grants Section Contact			
Name:	Nick Carr	Timothy Manglicmot			
Title:	Senior Planner	Acting Manager, Capital Procurement & Management			
Phone:	415-701-4468	415-646-2517			
Email:	Nick.Carr@sfmta.com	Timothy.Manglicmot@sfmta.com			